



## Notice of a public meeting of

### Planning Committee B

- To:** Councillors Hollyer (Chair), Melly (Vice-Chair), Craghill, Crawshaw, Daubeney, Fisher, Galvin, Orrell and Perrett
- Date:** Thursday, 11 August 2022
- Time:** 4.30 pm
- Venue:** The George Hudson Board Room - 1st Floor West Offices (F045)

### AGENDA

**1. Declarations of Interest**

At this point in the meeting, Members are asked to declare any disclosable pecuniary interest or other registerable interest they might have in respect of business on this agenda, if they have not already done so in advance on the Register of Interests.

**2. Minutes** (Pages 1 - 6)

To approve and sign the minutes of the last Planning Committee B meeting held on 08 June 2022.

**3. Public Participation**

At this point in the meeting members of the public who have registered to speak can do so. Members of the public may speak on agenda items or on matters within the remit of the committee. Please note that our registration deadlines have changed to 2 working days before the meeting, in order to facilitate the management of public participation at our meetings. The deadline for registering at this meeting is **5:00pm on Tuesday, 09 August 2022.**

To register to speak please visit [www.york.gov.uk/AttendCouncilMeetings](http://www.york.gov.uk/AttendCouncilMeetings) to fill out an online registration form. If you have any questions about the registration form or the meeting, please contact the relevant Democracy Officer, on the details at the foot of the agenda.

## **Webcasting of Public Meetings**

Please note that, subject to available resources, this public meeting will be webcast including any registered public speakers who have given their permission. The public meeting can be viewed live and on demand at [www.york.gov.uk/webcasts](http://www.york.gov.uk/webcasts) .

During coronavirus, we have made some changes to how we are running council meetings. See our coronavirus updates [www.york.gov.uk/COVIDDemocracy](http://www.york.gov.uk/COVIDDemocracy) for more information on meetings and decisions.

### **4. Plans List**

This item invites Members to determine the following planning applications:

**a) Land to the east of Middlewood Close Rufforth (Pages 7 - 64)  
[21/02661/FULM]**

Erection of 21 dwellings and associated works. [Rural West York]

**b) 29 Moor Lane [22/00872/FUL] (Pages 65 - 84)**

Single storey side and rear extensions after demolition of existing garage, and loft conversion with hip to gable roof, dormer to rear and 2no. rooflights to front (part retrospective). [Dringhouses and Woodthorpe Ward]

### **5. Urgent Business**

Any other business which the Chair considers urgent under the Local Government Act 1972.

Democracy Officer:  
Angela Bielby

Contact details:

- Telephone: (01904) 552599
- Email: [a.bielby@york.gov.uk](mailto:a.bielby@york.gov.uk)

For more information about any of the following please contact the Democratic Services Officer responsible for servicing this meeting:

- Registering to speak
- Business of the meeting
- Any special arrangements
- Copies of reports and
- For receiving reports in other formats

Contact details are set out above.

**This information can be provided in your own language.**

我們也用您們的語言提供這個信息 (Cantonese)

এই তথ্য আপনার নিজের ভাষায় দেয়া যেতে পারে। (Bengali)

Ta informacja może być dostarczona w twoim własnym języku. (Polish)

Bu bilgiyi kendi dilinizde almanız mümkündür. (Turkish)

یہ معلومات آپ کی اپنی زبان (بولی) میں بھی مہیا کی جاسکتی ہیں۔ (Urdu)

 **(01904) 551550**

This page is intentionally left blank



City of York Council

Committee Minutes

---

Meeting	Planning Committee B
Date	8 June 2022
Present	Councillors Hollyer (Chair), Melly (Vice-Chair), Craghill, Crawshaw, Daubeney, Fisher, Galvin and Perrett
Apologies	Councillor Orrell
Officers Present	Gareth Arnold – Development Manager Alison Stockdale – Development Officer Claire MacRae – City Archaeologist Sandra Branigan – Senior Solicitor

---

The Chair noted the change to the name of the Committee and thanked Cllrs Waudby and Webb for their service. He welcomed Cllr Melly as the new Vice-Chair and thanked the previous Vice-Chair, Cllr Crawshaw, for his service.

The Chair outlined the new meeting procedures which were contained in Appendix 17 of the new constitution.

### **1. Declarations of Interest (4:36 pm)**

Members were asked to declare at this point in the meeting any disclosable pecuniary interests or other registrable interests that they might have in the business on the agenda, if they had not already done so in advance on the Register of Interests.

Cllr Daubeney noted an personal, non-prejudicial interest in item 4a, as a communicant of All Saints Church, which was situated close to the site.

No other interests were declared.

### **2. Minutes (4:36 pm)**

Resolved: That the minutes of the last meeting held on 28 April 2022 were approved and signed by the Chair as a correct record.

**3. Public Participation (4:36 pm)**

It was reported that there had been no registrations to speak at the meeting under the Council's Public Participation Scheme.

**4. Plans List (4:36 pm)**

Members considered a schedule of reports of the Development Manager, relating to the following planning applications, outlining the proposals and relevant policy considerations and setting out the views of consultees and officers.

**5. Land To The Rear Of Mill House, North Street, York [20/02421/FULM] (4:37 pm)**

Members considered an application for the erection of hotel, associated works and infrastructure on land to the rear of Mill House, North Street, York.

The Development Manager gave a presentation on the application and Officers confirmed that the parking on the plan was associated with Mill House, the scheme was entirely car free and there was no disabled access parking for the hotel.

Members were provided with an update by the Development Officer:

The latest consultation responses from the Flood Risk Management Team were shared and responses to the submission of an indicative foundation plan from Design, Conservation and Sustainable Development (Archaeology) and Historic England were outlined.

The following additional conditions were noted:

29 The building shall not be occupied until the waste store has been provided within the site in accordance with the approved plans, and this area shall not be used for any purpose other than the storage of waste.

Reason: In the interests of amenity.

30 Prior to first occupation a Flood Evacuation Plan, based on the submitted Flood Evacuation Plan (dated February 2022) Ref REP02 (A), shall be submitted and approved in writing by the Local Planning Authority. The measures detailed within the approved flood evacuation plan shall be adhered to thereafter throughout the lifetime of the development.

Reason: To ensure the development is safe for its users in accordance with NPPF paragraph 167.

The following minor change was proposed to condition 21: No construction shall commence until a foundation design and statement of working methods for identifying and dealing with obstructions to piles has been approved in writing by the Local Planning Authority. The design must not cut off waterlogged deposits from the river. No intrusions other than pile caps **and beams**, lift pit and piles themselves will be permitted below 8.75m AOD. The foundation design will preserve at least 95% of the most significant archaeological deposits below the level of 8.75m AOD.

This condition was imposed in accordance with Section 16 of NPPF and City of York Historic Environment Policy D6.

Members were invited to put questions to the City Archaeologist and it was confirmed that:

- They had been unable to characterise the whole site as the 19<sup>th</sup> and 20<sup>th</sup> century layers needed to be removed first. Below the water table, the Anglo Scandinavian water logged deposits were of higher significance should be intact.
- It was accepted that the piling mat work had to be done and condition 21 was sufficiently robust to preserve at least 95% of the most significant archaeological deposits below the level of 8.75 metres. It had been conditioned that CYC could monitor the site up to five years post build.

#### Public Speaker

Killian Gallagher, the agent for the application, described the merits of the proposal and highlighted the sustainable credentials of the plans. He also explained that residents of the hotel would contribute to the local economy by eating out in the city as a bar or restaurant was not included within the plans.

In response to questions from Members, the agent and the architect confirmed the following:

- There was no parking on site, including for disabled access.
- An operator had not been identified for the hotel.
- It was expected that the user group would be made from businesses during the week and leisure couples at the weekend.
- The site was expected to exceed the Climate Change policies CC1 and CC2 within the local plan. To achieve a net zero build, the UK Green Building Council framework had been followed, this set out the method to calculate carbon emissions of both operational and embodied energy.
- Electric Vehicle (EV) charging points were within the red line boundary on the plan.

Officers responded to further questions from Members as follows:

- The City Archaeologist would monitor the site to ensure that condition 21 was achieved.
- The number of EV charging points were indicated on the plan, there was not a policy to collect a contribution toward EV points elsewhere. Condition 7 could be reworded to ensure that the EV charging spaces were accessible.

During the debate, the Senior Solicitor addressed the Committee to clarify the planning balance. She advised that the planning application must be considered on its own planning merits and, in the absence of an adopted development plan, the National Planning Policy Framework (NPPF) identified a 'tilted balance' which meant the presumption in favour of a sustainable development unless any adverse impacts had been considered to significantly outweigh the benefits. If there were any heritage concerns which had not been addressed by the public benefits test the planning balance would be different.

Following further debate, the Officer recommendation for approval was moved by Cllr Galvin and seconded by Cllr Fisher. A vote was taken and due to the Chair's casting vote it was:

Resolved: That the application be approved subject to an amendment to condition 7, to require details to demonstrate that the positioning of the EVCP (Electric Vehicle Charging Point) will not obstruct the use of the disabled parking bays.

Reason: The proposed redevelopment of the application site for a hotel was considered to be acceptable in principle given the city centre use. The proposal was acknowledged to be in highly sensitive location with a number of designated heritage assets in close proximity, and also being within the conservation area. The proposal, as a result of its design and scale, preserves the character and appearance of the conservation area and the setting of the listed buildings. Furthermore, the scheme provides a sustainable car free development and will help to meet the Council's ambitious climate change targets set out in Policies CC1 and CC2 of the 2018 Draft Plan. The proposal was considered to be a distinctive and positive design solution for the location and acceptable on amenity grounds.

Paragraph 11(d) of the NPPF states where there are no relevant development plan policies, planning permission should be granted unless the application of policies in the NPPF that protect areas or assets of particular importance provides a clear reason for refusing the development proposed or any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in the NPPF taken as a whole. This assessment concluded that, while the proposal will result in less than substantial harm to below ground heritage. Paragraph 202 of the NPPF requires that where a proposal will lead to less than substantial harm to the significance of a designated heritage asset, this harm should be weighed against the public benefits of the proposal. In this instance it was considered that the less than substantial harm was outweighed by economic and regeneration benefits. The proposed conditions would ensure acceptable mitigation.

## **6. Planning Appeal Performance and Decisions (4:37 pm)**

The Development Manager presented a report which provided information on the planning appeal decisions determined by the Planning Inspectorate between 1 January and 31 March 2022.

In response to questions from Members, Officers clarified that the Planning Inspectorate considered applications under the prevailing circumstances at the time of the appeal and did not therefore consider circumstances at the time of the application.

Resolved: That the report be noted.

Reason: To keep Members informed of the current position of planning appeals against the Council's decisions as determined by the Planning Inspectorate.

Cllr A Hollyer, Chair

[The meeting started at 4.32 pm and finished at 6.01 pm].

**COMMITTEE REPORT**

**Date:** 11 August 2022      **Ward:** Rural West York  
**Team:** West Area      **Parish:** Parish Of Rufforth with  
Knapton

**Reference:** 21/02661/FULM  
**Application at:** Land To The East Of Middlewood Close Rufforth York  
**For:** Erection of 21no. dwellings and associated works  
**By:** Rob Martin  
**Application Type:** Major Full Application  
**Target Date:** 9 March 2022  
**Recommendation:** Approve subject to Section 106 Agreement

**1.0 PROPOSAL**

1.1. The application site consists of a parcel of land covering approximately 1 hectare located to the east of Middlewood Close, Rufforth. The northern section of the site sits to the rear of existing residential properties on Middlewood Close. The southern section abuts the boundary of the existing playing field associated with Rufforth Primary School. The land immediately to the east of the application site is open agricultural land.

1.2. Vehicular access to the site would be via Middlewood Close, which in turn provides access to the B1224 Wetherby Road. At the point where Middlewood Close currently terminates, a field track continues in an easterly direction to provide access to an existing agricultural building approximately 500m away. There are no existing public rights of way within the vicinity of the site.

1.3. Planning permission is sought for the erection of 21.no dwellings and associated works. The proposed dwellings would be a mix of 2, 3 and 4 bed properties, a proportion of which will be affordable homes. The proposed accommodation mix comprises:

2 Bed House: 5 (2 Market, 3 Affordable);  
3 Bed House: 10 (8 Market, 2 Affordable);  
4 Bed House: 6 (5 Market, 1 Affordable).

Total: 21 (15 Market, 6 Affordable).

1.4. Since the original submission, amendments have been made to the scheme. Amendments include revisions to the house types and the accommodation mix proposed. A proposed pumping station originally shown as being to the east of the development, outside the extent of the proposed housing allocation known as H38, has now been relocated to the west of the site and would now be sited on land included within the housing allocation. Amendments have also been made to address and clarify matters relating to on-site parking provision and the internal highway layout in general.

## BACKGROUND AND RELEVANT SITE HISTORY

1.5. The application site has been identified as a housing allocation (site reference H38) within the Publication Draft Local Plan 2018, with an anticipated yield of 33 dwellings.

1.6. There is no planning history for the site considered to be relevant to the determination of this current application.

## 2.0 POLICY CONTEXT

### NATIONAL PLANNING POLICY FRAMEWORK

2.1. The revised National Planning Policy Framework (NPPF) was updated and re-published in July 2021 and sets out the Government's overarching planning policies for England and how these are expected to be applied.

2.2. Planning law requires that applications for planning permission must be determined in accordance with the development plan unless material considerations indicate otherwise (section 38(6) Planning and Compulsory Purchase Act 2004).

2.3. The statutory Development Plan for the City of York comprises the saved policies and key diagram of the otherwise revoked Yorkshire and Humber Plan Regional Spatial Strategy (2008) (RSS) and any made Neighbourhood Plan.

2.4. Although the RSS has otherwise been revoked, its policies relating to the York Green Belt have been saved, together with the Key Diagram insofar as it illustrates the general extent of the Green Belt around York. Saved policy YH9 states 'the detailed inner boundaries of the Green Belt around York should be defined in order to establish long term development limits that safeguard the special character and setting of the historic city. The boundaries must take account of levels of growth set out in the RSS and must also endure beyond the Plan period.'



2.5. The application site falls within the general extent of the Green Belt as shown on the Key Diagram of the saved RSS Green Belt policies.

## THE RUFFORTH AND KNAPTON NEIGHBOURHOOD PLAN

2.6. The Rufforth and Knapton Neighbourhood Plan was formally adopted in December 2018.

2.7. The adopted Neighbourhood Plan now forms part of the statutory Development Plan for the City of York. The policies contained within the Neighbourhood Plan are therefore material considerations in the assessment of planning application within the defined Neighbourhood Plan area and full weight can be given to the policies contained within the plan.

2.8. Key relevant Neighbourhood Plan Policies are:

- RwK 03 – Heritage
- RwK 04 – Biodiversity
- RwK 05 – Footpaths and Cycle Ways
- RwK 06 – Traffic Management
- RwK 08 – Parking
- RwK 09 – Drainage
- RwK 10 – Design
- RwK 11 – Community Amenities
- RwK 12 – Housing Mix

## PUBLICATION DRAFT LOCAL PLAN (DLP 2018)

2.9. The DLP was submitted for examination on 25<sup>th</sup> May 2018. Phase 3 of the hearings into the examination of the Local Plan took place in July 2022 with Phase scheduled for September 2022. In accordance with paragraph 48 of the NPPF the Draft Plan policies can be afforded weight according to:

- The stage of preparation of the emerging plan (the more advanced the preparation the greater the weight that may be given);
- The extent to which there are unresolved objections to relevant policies (the less significant the unresolved objections, the greater the weight that may be given); and
- The degree of consistency of the relevant policies in the emerging plan to the policies in the previous NPPF published in March 2012. (N.B: Under

transitional arrangements plans submitted for examination before 24 January 2019 will be assessed against the 2012 NPPF).

2.10. Key relevant DLP 2018 policies are:

DP2 – Sustainable Development  
DP3 – Sustainable Communities  
SS1 – Delivering Sustainable Growth for York  
SS2 – The Role of York’s Green Belt  
H1 – Housing Allocations  
H2 – Density of Residential Development  
H3 – Balancing the Housing Market  
H10 – Affordable Housing  
HW2 – New Community Facilities  
HW4 – Childcare Provision  
HW7 – Healthy Places  
D1 – Place Making  
D2 – Landscape and Setting  
D6 – Archaeology  
GI6 – New Open Space Provision  
CC1 – Renewable and Low Carbon Energy Generation and Storage  
CC2 – Sustainable Design and Construction of New Development  
ENV1 – Air Quality  
ENV2 – Managing Environmental Quality  
ENV3 – Land Contamination  
ENV5 – Sustainable Drainage  
T1 – Sustainable Access  
T7 – Minimising and Accommodating Generated Trips  
DM1 – Infrastructure and Developer Contributions

### **Emerging Local Plan evidence base**

2.11. The evidence base that underpins the proposed emerging policies is a material consideration in the determination of this planning application. The directly relevant evidence base is:

- City of York Housing Needs Update (2020).
- Strategic Housing Land Availability Assessment Figure 6: Updated to 790 dwellings per annum Objectively Assessed Need (2019).
- Topic Paper 1: Approach to defining York’s Green Belt (2021).
- City of York Local Plan Viability Assessment Update (2018).
- Strategic Housing Land Availability Assessment and Appendices (2018).

- Strategic Housing Land Availability Assessment and Annexes (2017).
- City of York Strategic Housing Market Assessment Update (2017).
- City of York Strategic Housing Market Assessment (2016).
- City of York Strategic Housing Market Assessment Addendum (2016).
- City of York Site Selection Paper Addendum (2014).
- City of York Local Plan Viability Study (September 2014).
- City of York Site Selection Paper and Annexes (2013).
- City of York Historic Character and Setting Technical Paper Update (2013).
- City of York Site Selection Paper and Annexes (2013).
- City of York Historic Character and Setting Technical Paper Update (2013).
- City of York Historic Character and Setting Technical Paper (2011).
- Approach to the Green Belt Appraisal and Maps (2003).

## DEVELOPMENT CONTROL LOCAL PLAN 2005 (DCLP)

2.12. The Development Control Local Plan (incorporating the Fourth Set of Changes) was approved for development management purposes in April 2005. The Plan does not form part of the statutory development plan for the purposes of S38 (6) of the Planning and Compulsory Purchase Act 2004. Its policies are, however, considered capable of being material considerations in the determination of planning application where policies relevant to the application are consistent with those in the NPPF although the weight that can be attached to them is very limited.

2.13. Paragraph 11 of the NPPF states that decisions should apply a presumption in favour of sustainable development which means, for decision taking:

- Approving development proposals that accord with an up-to-date development plan without delay; or
- Where there are no relevant development policies, or the policies which are most important for determining the application are out-of-date, granting permission unless:

- (i) The application of policies within this framework that protect areas or assets of particular importance provides a clear reason for refusing the development proposed; or
- (ii) Any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in this framework taken as a whole.

2.14. However, the presumption does not apply if the proposal conflicts with the more restrictive Green Belt policies as set out in the NPPF.

### 3.0 CONSULTATIONS

3.1. The application has been publicised by site notice, press notice and neighbour notification letter.

#### INTERNAL

3.2. AFFORDABLE HOUSING OFFICER: No objections raised but suggests the layout is adjusted to accord with the definition of 'pepper-potting' within Policy H10. A commuted sum will also be required, to the value of 0.3 of a dwelling, to achieve the 30% affordable housing provision.

3.3. CITY ARCHAEOLOGIST: The application site has been subject to intrusive archaeological evaluation. The results of the evaluation have confirmed the low archaeological potential of the site. No archaeology conditions are required.

3.4. TREE AND LANDSCAPE OFFICER: No objections raised. The revised layout and the proposed highway works better with the existing oak tree and is acceptable. The two existing trees make a good terminating feature at the head of the northwest cul-de-sac. Unit 6 and to a lesser degree unit 7 do look to be uncomfortably shoe-horned into the northwest corner of the site in relation to the existing vegetation.

The location, scale and containment of the site and the linear format of the village, visual impact of the development from Main Street and public rights of way is unlikely to be significant.

3.5. ECOLOGIST: No objections raised subject to conditions relating to nesting birds, a biodiversity enhancement plan and lighting plan.

3.6. HIGHWAYS: No objections raised subject to conditions regarding design and development of the access road and provision of cycle parking. The proposed layout of the development has been subject to various amendments throughout the process to make adjustments to the internal highway layout.

3.7. PUBLIC PROTECTION (ENVIRONMENTAL HEALTH): No objections raised but recommends the use of conditions relating to the management of the site during the construction phase, potential land contamination issues and the provision of infrastructure relating to the provision of electric vehicle charging points (EVCP).

3.8. LEAD LOCAL FLOOD AUTHORITY (FLOOD RISK): No objections raised and accepts the proposed discharge rate. The drainage condition will include the

requirement for approval of a topographical survey to ensure finished levels of the site are not raised above the level of the adjacent land.

3.9. PLANNING POLICY TEAM: Comments provided at pre-application stage. The site is an allocation in the submitted City of York Local Plan (2018). It is against the NPPF 2021 and the saved RSS policies relating to the general extent of the York Green Belt that this proposal should be principally assessed along with policies in the adopted Rufforth and Knapton Neighbourhood Plan. Notwithstanding the site's allocation within the emerging Local Plan, the site is located within general extent of York's Green Belt (as per 'saved' RSS policy illustrating the Green Belt's extent); and should be assessed as such.

3.10. EDUCATION: Request Education contributions totalling £192,234 to contribute toward expansion and facilities at Rufforth Academy and expansion at Manor School.

3.11. LIFELONG LEARNING AND LEISURE (OPEN SPACE): No objections raised. It is noted that the proposals would not provide any on-site amenity, play or sports pitch open space. As such off-site contributions would be required. Amenity open space contributions would be used to improve a facility in the village such as the allotments at Heights Lane. Play space contributions to improve a facility in the village either the play area to the village hall and/or the facility at Rufforth Playing Fields. The Sports contribution would go to the nearest sports organisations and these would be clubs at Rufforth Playing Fields namely, Rufforth Football Club, Rufforth Cricket Club and Rufforth Tennis Club.

3.12. CARBON REDUCTION TEAM: No objections raised noting that the submitted energy statement and low / zero carbon technology feasibility study has been provided showing an intent to meet the standards set out in CC1 and CC2. Recommend the use of conditions to achieve these.

## EXTERNAL

3.13. RUFFORTH WITH KNAPTON PARISH COUNCIL: No objections in principle but do have serious concerns with the proposals as submitted:

- The Parish Council stands by the position taken in the Neighbourhood Plan in support of a housing allocation on the proposed site, but we have serious concerns that if planning permission is granted before the extent of the Green Belt is legally redefined a dangerous precedent will have been created.
- In the submission version of the Neighbourhood Plan the site was allocated for housing subject to some strict criteria which were agreed with the landowner.

These were: properties should be predominantly 2, 3 and small 4 bed houses with adequate off-road parking or garaging to be provided removing the need for on street parking. A rear pedestrian entrance should be provided to encourage parents to use this new access alleviating the current parking pressures at school opening and closing times in Middlewood Close and Yew Tree Close. Attenuation tanks for both sewerage and surface water be constructed to ensure existing pressure on the system is not increased and hopefully reduced. Covenants be sought on properties to prevent further paving over gardens.

- A new pedestrian access to the rear of the school is an essential condition of approval of this application. Middlewood Close and Yew Tree Close already experience severe parking congestion at school opening and closing times and a rear entrance to the school from the development proposed development would encourage parents to use this access (away from the busy B1224) and spread parking over a wider area.
- Residents in the area already experience severe problems with sewerage with frequent blockages and it is our contention that the current infrastructure is not fit for purpose. It is not sufficient to ensure that the sewerage installation for the new development is sufficient for the new houses but rather the system in that area needs complete renewal.
- The pumping station and temporary silo are located outside of the proposed development and on Green Belt land.
- Construction should commence no earlier than 08:00 for the benefit of local residents. Also there should be a commitment to avoid deliveries and the movement of HGVs during school opening and closing times.
- A riding facility is located next to the proposed site and conditions will be required to avoid disturbance and risks to horses and riders.
- The cycle path between Rufforth and Knapton is totally unlit and is shared recreational cycleway, footpath and bridleway passing through open and wooded countryside making it totally unsuitable as a potential cycling commuter route.
- The B1224 is an extremely busy road and is therefore unsafe as a cycling commuter route. The bus service through the village amounts to one every 2 hours and timing is often unreliable. As such a car is essential for residents of Rufforth.
- The Parish very strongly believes that the CYC parking standards referred to in the highways response are based on assessment of City needs. Rufforth is not in the city but a rural community six miles from the city centre as such the parking standards are totally inadequate. Parking provision by the developer is the absolute minimum and should not be reduced in any circumstances.

- We strongly believe that the whole of the private drive areas should be adopted highway which would enable additional parking to relieve the pressure on other roads at school opening and closing times.

3.14. AINSTY INTERNAL DRAINAGE BOARD: The application site sits within the Drainage Board's district. The Board has assets in the wider area in the form of various watercourses. These watercourses are known to subject to high flows during storm events. No objections raised but does request the use of conditions in the event of permission being granted. These relate to ensuring that suitable and adequate drainage provision can be achieved on site.

3.15. YORKSHIRE WATER: No objection, advise the drainage assessment issued in November 2021 is acceptable.

#### **4.0 REPRESENTATIONS**

4.1. A total of 12.no objections and 4.no representations had been received at the time of writing, including representation from the Ward Councillor.

4.2. Summary of the objections received:

##### **Principle of Development:**

- The York Local Plan is under review. It is important that this review is completed to avoid encroachment onto the Green Belt and associated environmental damage.
- The current presumption is development on greenfield land identified as reference H38. The consideration that has been given to brownfield sites within the city by the developer is not properly explained.
- The development is not an acceptable use of the Green Belt.
- The land is currently Green Belt and as such is not available for housing.
- This should remain Green Belt and is not suitable for any form of development.

##### **Traffic:**

- The road is very narrow and already suffers from congestion. Local children would be unable to play out and would also cause great disturbance to residents.
- The majority of properties proposed will have two cars as existing public transport is poor and cannot be relied upon.

- Rufforth is a commuter village and the majority of the working population commutes to surrounding towns (York, Leeds, Harrogate) and this development will add to already congested roads.
- Close proximity to the school means Middlewood Close is used by parents when dropping off and collecting children and also when events are held at the school; this already causes problems for existing residents.
- 21 houses would equate to at least 30 plus cars using the road.
- The road on Middlewood Close has deteriorated significantly since its use by heavy lorries for the pig unit.
- The road is unsuitable for these lorries and will be damaged further with additional traffic. There needs to be a plan to upgrade the road for additional traffic before and after the construction of the development.
- The speed limit of 30mph is inappropriate and dangerous if a through road is to be provided. Middlewood Close is used by children and pedestrians who often have to walk on the road due to inappropriate parking during school collection times.
- Any disruption during the build phase needs to be minimised.
- Insufficient parking.
- Much is made of expecting new residents to walk/bike or go by bus. Buses through the village are only once every two hours. Driving to the Park and Ride negates the green ethos.
- Traffic is already too much from the existing pig farm.
- High volumes of traffic already pass through the village.
- Proximity to the school heightens road safety issues.

### **Drainage:**

- Existing sewage disposal is poor and this will only make matters worse
- There are drainage issues on Middlewood Close.
- During heavy rain there is substantial standing water on the field and adjacent gardens.
- There are historic concerns with the capacity of the main sewer that runs at the back of the existing houses. Yorkshire Water are frequently called to unblock this.

### **Ecology:**

- The site has very established hedgerows that offer habitat to a wide range of species. The environmental assessment does not properly consider these hedgerows dismissing them as unimportant.
- The protection of established trees, hedgerows, protected species should be considered.



- The removal of trees and hedges endangers wildlife.

**General:**

- Proposals would more than double the current housing.
- Complete loss of amenity
- Building work would render an existing riding area unusable owing to heavy machinery operating nearby and unpredictable noises during construction and subsequent occupation of the houses.
- This will set a precedent to develop further in the village.
- There will be significant impacts upon the residents of Middlewood Close, the school and entire village.
- It is unclear what efforts the developer has taken to seek the views and opinions of residents, this causes concerns about the developer's commitment to being a considerate constructor.
- The density of housing does not appear in keeping with the existing.
- The Construction Environmental Management Plan lacks precision.
- No adequate provision for bins and recycling boxes has been made.
- Could the school cope with additional children?
- The houses are not needed in the village as there is plenty of housing stock.
- As councillors you are public servants and as such you must do as the residents of Rufforth require which is to deny planning permission for this application.
- Existing amenities in the village are extremely limited.

4.3. Summary of the representations received:

- Construction of the site should not cause excess noise.
- Traffic movements, especially large vehicles, should not be permitted when there are significant numbers of pedestrians such as school opening/closing times.
- Sufficient on-site parking needs to be provided. Rufforth is a rural village not well served by sustainable transport links.
- The creation of a rear entrance to the school is vital. Pavements to the front of the school are too narrow.
- This development should not compromise the limits of the Green Belt in the Draft Local Plan and that there is no possibility of setting a precedent for future development in the Green Belt.

**5.0 APPRAISAL**

## Key Issues

5.1 The key issues are as follows:

- Principle of Development
- Highways and Access
- Design and Layout of the site
- Residential Amenity and Public Protection
- Affordable Housing
- Drainage & Flood Risk
- Archaeology
- Ecology
- Sustainable design and construction
- Planning obligations
- The case for very special circumstances

## PRINCIPLE OF DEVELOPMENT

5.2 For the purposes of s.38(6) Planning and Compulsory Purchase Act, the proposals should be assessed against the saved RSS Green Belt polices and the adopted Rufforth with Knapton Neighbourhood Plan. Polices contained within the National Planning Policy Framework are also material considerations.

5.3. The 2005 DCLP shows the village of Rufforth and the land surrounding it as being 'washed over' Green Belt, meaning that the whole of the village and the land which now forms the subject of this application would be located within the general extent of the Green Belt. In contrast, in the emerging 2018 Local Plan, the village would be excluded from the Green Belt and the defined settlement limits would incorporate both the existing developed extent of the village and the application site. Thus the site would not fall within the Green Belt, and the resulting Green Belt boundary would about the eastern and south eastern boundaries of the application site.

5.4. However, it is the Local Planning Authority's position that until a Local Plan for the City of York is adopted, development management decisions relating to proposals falling within the general extent of the Green Belt are made on the basis that the land should be treated as Green Belt. For this reason, NPPF Green Belt policies apply to the determination of development proposals.

5.5. Paragraph 147 of the NPPF states: 'Inappropriate development is, by definition, harmful to the Green Belt and should not be approved except in very special circumstances'. Paragraph 148 goes on to state: 'When considering any

planning application, local planning authorities should ensure that substantial weight is given to any harm to the Green Belt. 'Very special circumstances' will not exist unless the potential harm to the Green Belt by reason of inappropriateness, and any other harm resulting from the proposal, is clearly outweighed by other considerations'.

5.6. Paragraphs 149 and 150 of the NPPF lists exceptions where new buildings are not inappropriate in the Green Belt. The proposed development would not meet any of the defined exceptions set out within paragraphs 145 and 146 of the NPPF. As a result, the proposals would in this context be considered to amount to inappropriate development within the Green Belt. As outlined earlier in this report, the Rufforth with Knapton Neighbourhood Plan has been adopted. Policy Rwk01 – Draft Green Belt is of relevance here. Policy Rwk01 sets out the same general parameters to those now contained within Paragraphs 149 and 150 of the NPPF.

## IMPACT UPON THE OPENESS OF THE GREEN BELT

As set in paragraph 137 of the NPPF, the essential characteristics of Green Belts are their openness and their permanence. There is no definition of 'openness' in the NPPF. However, it is commonly taken to mean the state of being free from development and relates to the quantum and extent of development and its physical effect on the site.

5.7. Policy GB1 of the 2018 Draft Plan states that permission will only be granted for development where:

- i. The scale, location and design of development would not detract from the openness of the Green Belt;
- ii. It would not conflict with the purposes of including land within the Green Belt; and
- iii. It would not prejudice or harm those elements which contribute to the special character and setting of York.

5.8. There are unresolved objections to the Policy GB1 that will be considered through the examination in public of the Local Plan and therefore it should only be afforded limited weight in the decision-making process for the purposes of this application.

5.9. The application site comprises of a broadly rectangular parcel of land which is currently grassland. The land is bisected by a track which provides access

from Middlewood Close to an agricultural unit located to the northeast of the site. The proposals would, due to their nature, reduce the openness within this part of the Green Belt. However, the extent of any such impact upon the overall openness of the Green Belt is considered to be limited.

5.10. The visual impact of the proposed development would be most noticeable in close proximity to the site and the surrounding roads, lanes and footpaths within the immediate vicinity of the site, creating a localised loss of openness. This impact will diminish further away from the site as the wider visual context provided by the existing built form and extent of Rufforth will begin to contribute to the wider setting of the development. The proposed development would lead to a degree of harm to the openness of the Green Belt.

## IMPACT ON THE GREEN BELT PURPOSES

5.11. Paragraph 138 of the NPPF sets out the five purposes of the Green Belt. These are:

- a) To check the unrestricted sprawl of large built up areas;
- b) To prevent neighbouring towns margining into one another;
- c) To assist in safeguarding the countryside from encroachment;
- d) To preserve the setting and special character of historic towns; and
- e) To assist in urban regeneration, by encouraging the recycling of derelict land and other urban land.

5.12. The primary purpose of the York Green Belt is to safeguard the special character and setting of the historic city as referred to in Policy YH9C of the RSS and Policy SS2 of the 2018 DLP, although moderate weight can only be attached to the latter.

5.13. The proposals would be situated to the east of Wetherby Road and continue the existing pattern of development that characterises the village, consisting of cul-de-sacs and side streets forming extensions of the main ribbon of development fronting onto Wetherby Road. The proposals would also preserve the setting and special character of the city of York. The design and layout would be in keeping with the existing grain of the village and allow the village to retain the character of a rural village surrounded by open countryside. It is therefore considered that the proposals would not conflict with 4 out of the 5 purposes of the Green Belt, namely a,b,d and e above.

5.14. The site is at the edge of the existing settlement, in agricultural use and not previously developed. As such the proposals would lead to a degree of encroachment into the countryside and would therefore be in conflict with purpose c) of NPPF Paragraph 138. However in considering the extent to which there is an adverse effect the proposed Green Belt boundaries in the 2018 DLP are relevant. The boundaries are informed by the Local Plan Green Belt Topic Paper (2021). In applying the methodology within the topic paper, analysis has arrived at the conclusion that the land in question can form part of the settlement and accommodate development in the form of the H38 Housing Allocation. The site can accommodate development without detrimental impact on the most important components of the York Green Belt, landscape character and role the countryside has in preserving the setting and special character of York, including the village of Rufforth.

## **HIGHWAYS & ACCESS**

5.15. The access to the site would form an extension of Middlewood Close, which itself is accessed directly from Wetherby Road. At present, Middlewood Close terminates at a field gate which provides access via a track to an agricultural unit to the east of the application site. As part of the development, it is proposed that this access will be maintained with the field gate being relocated to the eastern boundary of the application site.

5.16. Policy T1 of the 2018 Draft Local Plan states that development will be supported where it minimises the need to travel and provides a safe, suitable and attractive access for all transport users to and within it.

5.17. Since submission, the layout has been subject to various amendments which have included revisions to parking provision within the site and the provision of features such as cycle storage.

5.18. Connectivity into the existing highway network will be achieved by linking the site to Middlewood Close which in turn has direct access to Wetherby Road. Highways officers have not raised objections to the proposals. Given the overall scale of the proposals, it is not anticipated that the increase in traffic would result in highway capacity or highway safety issues on the surrounding network.

5.19. Each of the dwellings within the development will as minimum be provided with off-street parking commensurate with the size of the dwelling it would serve; these would consist of a mixture of in-curtilage driveways and garages and some detached parking spaces. Visitor spaces will be provided within the

development. The level of parking to be provided is considered acceptable in this case, with a degree of overprovision for some dwellings. Amongst comments received concerns have been raised about needing to ensure that adequate parking is provided and reflects the fact that the village is not served by a high frequency bus service. Cycle storage is to be provided at each dwelling. This will allow residents to suitably store cycles at the properties.

- 5.20. The details submitted to date indicate that the development would utilise a 6.5m wide shared surface road. In this scenario, rather than there being a traditional kerbed footway alongside a roadway, a shared surface would serve the needs of both vehicles and pedestrians. Separate space within the highway is not allocated to vehicles and pedestrians, and a varying pallet of materials and surfacing finishes are used in order to offer an element of demarcation between footway and roadway. Given the overall scale of this development, highways officers have advised that this approach would be acceptable under current highway design guidance, however further detail and clarification on certain matters is still required. Therefore, in the event of planning permission being granted, the final layout and design of the highway, in addition to the materials to be used, would be subject to a condition.
- 5.21. Highways officers have also recommended that a number of other conditions be imposed. These include full details of the vehicle access to be submitted and approved, details of the surfacing materials to be used, details of cycle parking to be agreed, a condition ensuring that the agreed car and cycle parking is laid out in accordance with the approved details prior to occupation, and details of the internal road layout to be agreed, including any areas which may be put forward for adoption by the Local Highway Authority. A condition requiring a construction traffic management plan is also recommended.
- 5.22. Collectively these conditions will also ensure that adequate parking, servicing and access arrangements are achieved without giving rise to highway safety concerns. The provision of a construction traffic management plan is considered necessary in this case given the close proximity of the site to an existing school.

#### Provision of a secondary access to Rufforth Primary School

- 5.23. Within the representations received, including those from the Parish Council, the issue of the provision of an additional means of access to the existing school site has been raised. As can often be the case with school premises there is a significant peak in traffic in and around the school when pupils are dropped off and collected from the school. This leads to busier periods of

traffic and parking on the roads and streets within the vicinity of the school. This issue is perhaps exacerbated to a degree, in this case, by a higher proportion of pupils attending the school from outside of the village leading to a higher prevalence in the use of private cars. The provision of an additional rear access to the school, it is argued, would encourage the parking of vehicles over a wider area and thus reduce the pressures upon Middlewood Close. Such an access would also avoid the need for pupils to negotiate the footpath along the B1224, Wetherby Road.

5.24. The section of Wetherby Road outside of the primary school is a 30mph section with chicanes located on both sides of the road. A Zebra crossing is also situated immediately outside the main pedestrian entrance to the school.

5.25. It is not reasonable, or desirable in place-making terms for this residential scheme to be designed to accommodate car parking for the school. Considering this matter in closer detail it becomes apparent that there are also several other matters and considerations which would be relevant. It is not a simple case of providing an additional access to the serve the school. Firstly, there is the issue of the location of such an access. The Parish Council and the School Governors would prefer the access to be located somewhere along the south western boundary of the application site, as this would provide a direct line of sight between the access and the main school building. However, in this location the access would need taken from an area of the development which is shown to be private driveway, which presents potential issues around rights of access and ultimately ongoing maintenance. Furthermore, the space within the development for the parking of additional or visiting vehicles and the layout of the space does not appear conducive to such uses. The access would then, within the school site, either need to cut directly across the existing playing fields which would be problematic in the context of impacting upon an existing playing field (which would likely be an issue of concern or objection from national bodies such as Sport England) or navigate the perimeter of the school site to avoid bisecting the playing field; this would require more resources to construct and may not achieve the direct line of sight principle.

5.26. An alternative location could be adjacent to the proposed access to the development within the vicinity of No.11 Middlewood Close. The obvious advantage to this location is that it could be taken directly from the extent of the existing adopted highway, mitigating issues around ongoing and future maintenance. However, this location would be outside of the extent of the application site, is unlikely to satisfactorily address concerns around peak time parking on Middlewood Close and would disproportionately impact upon the

amenity of the occupants of No.11. This location would also not meet the criteria applied by the Parish Council and the School Governors of providing a direct line of sight between the access and the school building.

5.27. Another key aspect of assessment as to whether a secondary access to the school should be secured is the scale of the development that is proposed. As is noted elsewhere in this report, the proposals are not anticipated to bring a material increase in the number of children attending the school. Furthermore, the provisions of paragraphs 56 and 57 of the NPPF are of relevance. Paragraph 56 states that planning conditions should be 'only imposed where they are necessary, relevant to planning and to the development to be permitted, enforceable, precise and reasonable in other respects. Paragraph 57 then goes on to state, in relation to planning obligations, that they must only be sought where they meet all of the following tests:

- a) Necessary to make the development acceptable in planning terms;
- b) Directly related to the development; and
- c) Fairly and reasonably related in scale and kind to the development.

5.28. The potential provision of a secondary pedestrian access to the school is not without its merits. The issue, within the context of assessing this particular planning application, is whether there are reasonable and justified grounds to require such works as part of this development and are such works required in order to make the proposed development acceptable in planning terms. In this case, it would not be reasonable to require the provision of such infrastructure, nor would the absence of such works likely make the development unacceptable in planning terms.

## **DESIGN AND LAYOUT OF SITE**

5.29. Paragraph 130 of the NPPF states that planning policies and decisions should ensure that developments:

- a) Will function well and add to the overall quality of the area, not just for the short term but over the lifetime of the development.
- b) Are visually attractive as a result of good architecture, layout and appropriate and effective landscaping.
- c) Are sympathetic to local character and history, including the surrounding built environment and landscape setting, while not preventing or discouraging appropriate innovation or change (such as increase densities).



- d) Establish or maintain a strong sense of place, using the arrangement of streets, spaces, building types and materials to create attractive, welcoming and distinctive places to live, work and visit.
- e) Optimise the potential of the site to accommodate and sustain an appropriate amount and mix of development (including green and other public space) and support local facilities and transport networks.
- f) Create places that are safe, inclusive and accessible and which promote health and well-being, with a high standard of amenity for existing and future users and where crime and disorder, and the fear of crime, do not undermine the quality of community cohesion and resilience.

5.30. National Planning Practice Guidance refers to the National Design Guide, which sets out the characteristics of well-designed places and illustrates what good design means in practice. The document can be used for decision-making. Policies D1 (Placemaking) and D2 (Landscape) of the emerging plan also cover design principles.

5.31. Many of the villages surrounding York show patterns of incremental growth from an original historic centre. Rufforth is no different in this regard. However it has perhaps retained a higher degree of its original 'ribbon development' characteristic than other settlements. This is also reflected in its general overall size and scale as a settlement. The oldest buildings within the village typically front Wetherby Road. Later developments have then taken place to the rear of these properties and as former farmyards have been developed. The result is a series of cul-de-sac type developments, typically of relatively modest scale, all accessed from Wetherby Road. However the historic ribbon character of the village is still clearly discernible.

5.32. The proposed development is considered to respect local character in terms of layout, scale and density. The proposed development consists of a mixture of 2, 3, and 4 bed dwellings, all of which are two storey units and predominantly detached or semi-detached. A single terrace of three units is proposed toward the southwestern boundary of the site. The exact specification of external materials and finishes to be used in the development has not been specified. However, the submitted details indicate that a mix of red-multi brick, stone and cream render would be utilised to achieve a cohesive appearance. Roofs are to be finished with slates or pantiles. In the absence of exact specifications being provided, in the event of planning permission being granted, it would be appropriate to attach a condition requiring details of exterior materials and finishes to be submitted for the approval by the local planning authority.

- 5.33. Within the details submitted, the proposed boundary treatments have been specified. These include the use of 1.8m high timber fences and walls. The timber fences would typically be used between the residential units to divide and demarcate private amenity spaces. Walls will be utilised in instances where the boundary faces what would be the public realm areas of the development (plots 1 & 16). Brick screens with piers and brick piers with knee high rails will be utilised to demarcate the transition between areas of highway and areas of private driveways. Some units will also benefit from 1.2m high 'estate railings' to enclose their front gardens. The proposed boundary treatments are considered to be acceptable in striking a balance between creating a visually cohesive appearance and also ensuring each dwelling is afforded suitable levels of privacy and security.
- 5.34. The design of the proposed dwellings is such that they would have a rural character; plots 19-21 have been designed as barn conversions utilising large ground floor openings with simpler, more subservient openings at first floor level with some use of small dormer type structures cut into the roof form. Overall, the general design and character of the proposals is considered to be in keeping with the existing wider built environment.
- 5.35. The site in its totality measures approximately 1 hectare. Policy H1 of the emerging plan specifies that the application site is anticipated to have yield of 33 dwellings. However, as is noted within the comments provided the Councils Forward Planning section, the yields set out within policy H1 do not reflect a detailed site assessment, instead they are a guide to potential deliverability based on a standard calculation of 35 dwellings per hectare (dph) across 90% of the developable area of the site.
- 5.36. Whilst acknowledging the importance of the site in delivering against the Plan's housing trajectory, negotiation should allow for reduced housing delivery to accommodate identified constraints, and to deliver against other stated policy principles, including affordable housing provision and housing mix.
- 5.37. The proposal for a total of 21 no. dwellings would equate to a development density of 21 dph. This would be approximately 40% below the target development density set out within Policy H2 of the emerging plan. However, in this case it is proposed that the existing trees and hedgerows on the site would be retained, save for some minor pruning. When this is factored in along with need for access and general landscaping to be provided the net developable area of the site is approximately 0.69 hectares. This equates to a development density of approximately 30.4 dph.

- 5.38. The development density that would be achieved on this development (30.4dph) is below the target figure set out within Policy H2 of 35dph. However, as is set out in this report, the development would deliver the required proportion of affordable housing units in an appropriate housing mix. The proposals also allow for much of the existing mature vegetation and trees around the perimeter of the site to be retained, which will assist with softening the transition from the built extent of the settlement into the more sparsely developed agricultural land that surrounds the village and which forms part of the general extent of the Green Belt. It is also considered that the proposals respond to the existing character of development within the village.
- 5.39. The NPPF states that developments should create places that are safe, inclusive and accessible and which promote health and well-being, with high standard of amenity for existing and future users; and where crime and disorder, and the fear of crime, do not undermine the quality of life or community cohesion and resilience. The proposed layout provides a number of opportunities for natural surveillance, with all units fronting the main access route into the site. All units will benefit from external access to private amenity spaces and these spaces will be enclosed by fences and gates.
- 5.40. A proposed landscaping plan has been submitted. This will provide additional tree planting to be incorporated into the development which will add to the existing trees and vegetation which already provide a setting to the site. In order to ensure that this landscaping is secured along with providing an adequate time period within which to allow the planting to mature it would be necessary to condition implementation of the proposed landscaping. In addition to this it would also be appropriate to condition tree protection measures are utilised during the construction phase of development to ensure that the trees to be retained are afforded suitable protection.
- 5.41. Overall, there it is considered that the proposals would provide a suitable layout which facilitates development whilst also accommodating the more detailed constraints of the site. The proposals are therefore considered to accord with policies D1 and D2 of the DLP.

## **RESIDENTIAL AMENITY & PUBLIC PROTECTION**

- 5.42. The internal layout of the development is such that the proposed dwellings would be arranged in a manner to ensure that future occupants do not experience unacceptable levels of overlooking or overshadowing which would be harmful to amenity.

- 5.43. With regard to the existing properties and land uses which surround the site, the closest neighbouring residential properties to the proposed development are those situated to the southwest of the site on Middlewood Close, approximately 40m away, and the property known as Woodlands which is situated beyond the northern boundary of the site at a distance of approximately 33m. As a reference, a 21m rear-to-rear separation distance between two storey dwellings is generally considered to be appropriate and is the recommendation set out within the Council's Supplementary Planning Document on Extensions and Alterations to dwellings. Given the separation distances that would be achieved to existing properties it is not considered that the proposals would give rise to issues of overlooking or overshadowing which could be detrimental to the residential amenity of the existing residents. Nor is it considered that the proposals would have a particularly overbearing impact upon existing properties.
- 5.44. The Council's Public Protection Team have reviewed the proposals and have not raised any objections. They have however requested that a series of conditions be attached to any planning permission, and these are set out in greater detail below.
- 5.45. With regard to noise there are existing uses close to the application site, namely the agricultural building (pig unit) to the northeast and horse riding arena to the south. Both these existing uses have the potential to give rise to noise disturbance that could impact upon future residents of the proposed development. The applicant has provided details on the current usage of the pig unit. The unit is used as a temporary isolation unit for the purposes of disease control away from the breeding stock held at the main farm, and is semi-automated and requires minimal daily input. Active operation of the site is therefore minimal. Vehicle movements are limited to a tele-handler for moving bales. Animals are transported in a trailer pulled by a pickup truck and movements to and from the facility are every two months.
- 5.46. The neighbouring horse-riding facility is used for domestic purposes only. This use is restricted via a condition attached to the associated planning permission for the premises (Ref: 09/00548/FUL). As such the use of this facility is significantly less intense than a commercial livery type operation. Amongst the objections received to the proposals, concerns have been raised with regard to the potential noise impact the development may bring upon the existing stables and riding area. As with any construction work, there is the potential for a degree of disturbance and disruption to be caused. However, in this case it is considered that any such disruption can be suitably managed. Regarding

the potential for disturbance post-construction, the relationship of the two closest dwellings, whilst closer than the existing dwellings on Yew Tree Close and the existing primary school, is not considered to significantly change the existing situation to such an extent that would warrant the refusal of planning permission on such grounds. Public Protection have therefore concluded that in this case there is no requirement for a noise assessment to be undertaken, nor is there a requirement for any conditions pertaining to noise control.

- 5.47. As part of the supporting documentation submitted by the applicant an odour assessment has been provided. This assessment has concluded that the neighbouring land uses of the pig unit and the equine facility will not have a significant impact upon the proposed residential development in respect of odour.
- 5.48. As with any construction works there is the potential for a degree of disruption to be caused during the construction phase. However, given the overall scale of the development, any such disruption would, within the context of the lifetime of the development, be relatively short lived. Nevertheless, it is still necessary to ensure that this construction phase is appropriately managed so as not to cause undue disruption or safety issues to the surrounding area, as is required by policy ENV2 of the emerging DLP.
- 5.49. The applicant has, as part of the submission, provided a Construction Environmental Management Plan (CEMP). However, colleagues in Public Protection advise that this submission is deficient in certain aspects, namely that the proposed construction hours do not accord with those normally imposed by the local planning authority and that the submitted CEMP does not consider any piling works that may be undertaken. As such Public Protection have advised that, in the event of granting planning permission, it would be necessary to condition that an amended CEMP be submitted to the local planning authority, for approval, prior to the commencement of development.
- 5.50. As part of the development the applicant is proposing the provision of electric vehicle (EV) charge points. All dwellings will either have an in-curtilage EV charge point or will have access to a remote EV charge point (via combined charger/bollard light). However, at this stage no precise details of this infrastructure have been provided. For this reason, it is considered appropriate to condition that details of the EV charge points to be provided are submitted and agreed in writing prior to the occupation of the dwellings. This condition will assist with delivering the objectives of CYC's Low Emissions Strategy and also accord with Paragraph 112 of the NPPF both of which aim to promote the uptake of EVs and other low/ultra low emission vehicles.

5.51. The application is supported by a Geo-environmental Investigation report. This report has demonstrated that the site is suitable for the proposed development and that the site does not present significant potential contaminant linkages. Notwithstanding this, there remains a potential for unexpected land contamination issues to be discovered on site during construction. It would therefore be appropriate to include a condition covering unexpected land contamination. This would provide a suitable mechanism by which any unexpected land contamination that is encountered at the site can be recorded and where necessary be remediated. This condition will provide suitable safeguards to the health and well-being of future occupants and ensure suitable environmental protections are secured should there be any land contamination issues.

## **AFFORDABLE HOUSING**

- 5.52. Policy H10 of the emerging Local Plan sets affordable housing thresholds. These vary depending upon the category of site involved. In this particular case, the site is a greenfield site where more than 15 units are proposed. As a result, the relevant threshold in this case is 30%. Given that the proposal is for 21.no units a 30% affordable housing provision would equate to 6.3 units.
- 5.53. The development will include the provision of 6.no affordable units. These would comprise of 3 no. two bed units, 2 no. three bed units and 1 no. four bed unit. Two of the units (1x 3 bed and 1x 4 bed) would be available via shared ownership with the remainder being rented.
- 5.54. The 6.no affordable units on the development would equate to an on-site affordable housing provision of 28.57%. To achieve 30% affordable housing provision, the payment of a commuted sum would be necessary. This payment would be secured by means of a Section 106 Agreement and be used toward the provision of affordable housing within the CYC authority area. The exact figure for this commuted sum would be calculated using a standardised calculation methodology.
- 5.55. Policy H10 (v) states that affordable housing provision should: ‘fully integrate, by pepper potting throughout the development with no more than two affordable dwellings placed next to each other. The size and type of homes should be a pro-rata mix of the total homes provided on site, taking into account current assessments of local need where on-site provision is required.

The affordable housing should be visually indistinguishable from the open market dwellings’.

- 5.56. From a visual perspective the design of the proposed affordable units would be in keeping with those on the wider development. The proposed layout of the units consists of a row of three dwellings (plots 1-3), 1 detached dwelling (plot 7) and a pair of semi-detached dwellings (plots 8 & 9). This layout would result in two instances of 3 affordable units being located next to one another. Whilst this layout would not strictly accord with the provisions of Policy H10 (v), it is considered acceptable in this instance. Securing strict adherence to such a layout requirement would be likely, given the relatively modest scale of the site, to give rise to other impacts elsewhere such as having to remove existing landscaping features or other infrastructure which is required as part of the development. As such the proposed dispersal of affordable housing units is considered to be acceptable.
- 5.57. Overall, the proposed affordable housing provision is considered to accord with the provisions of Policy H10 of the emerging local plan. The provision of affordable units will make a contribution to the affordable housing stock within the city. It will be necessary to include provision of these units through an associated Section 106 agreement to ensure that they are delivered and set out the necessary frameworks and mechanisms for the units to be transferred to a suitable registered provider.

## **DRAINAGE & FLOOD RISK**

- 5.58. The application site is located within flood zone 1 (low risk) as defined by the Environment Agency. In flood risk terms the development is (sequentially) appropriate in this location. The general objective of the NPPF with regard to flood risk is that development should not increase flood risk elsewhere. Policy ENV5 of the DLP advises that sustainable drainage should be implemented unless this is not feasible. Detailed local requirements are set out within the Sustainable Drainage Systems Guidance for Developers (2018).
- 5.59. Amongst the objections received, concerns have been raised about continued and historic issues relating to the existing sewerage infrastructure in the immediate area, with reports that technicians from Yorkshire Water have had to attend to issues in the locality on numerous occasions. The site at present is greenfield (undeveloped) and as such does not benefit from any active drainage infrastructure.

- 5.60. As part of the development a pumping station is proposed. Since submission this has been re-located so as to be within the extent of the application site. The submitted topographical survey shows that the site is relatively flat with existing ground levels varying from approximately 16.37m AOD to 15.5m AOD. The surface water run-off rate for the site is agreed.
- 5.61. Site investigations have already confirmed that soakaways as a means of surface water disposal are not suitable on this site. This is due the existing subsoil conditions which are predominantly overlaid with dense clay. Foul water waste is proposed to be discharged to the existing sewer located to the west of the site. The submitted Flood Risk and Drainage Assessment acknowledges that a gravity discharge to the public sewer will not be achieved, hence the inclusion of pumping station within the proposals.
- 5.62. It will be possible to achieve an acceptable technical solution with regard to the drainage of the proposed development without giving rise to increasing flood risk within the vicinity of the site. However, to ensure that this is the case it would be necessary to secure such infrastructure by condition. The conditions will require that the site is development with separate systems of drainage for foul and surface water on and off site. A second condition will also require that full details of the proposed means foul and surface water drainage, including any balancing works, be submitted to and approved in writing by the local planning authority prior to the commencement of any development on site.
- 5.63. Neither Yorkshire Water nor the Ainsty Internal Drainage Board (IDB) have raised objections to the proposals but have requested that in the event of planning permission being granted conditions are imposed to secure suitable drainage provision. In both cases the requested conditions would achieve the same outcomes as set out above. It should be noted that these conditions would not negate the need for the applicant to secure other relevant approvals and consents from both Yorkshire Water and the IDB.
- 5.64. Subject to the use of the suggested conditions it is considered that the proposals would accord with the provisions of the NPPF and Policy ENV5 of the DLP 2018.

## **ARCHEOLOGY**

- 5.65. At the time of submission the application was accompanied by a desk based assessment and geophysical survey of the site. The site has not been subjected to any development in the past. As such the archaeological potential



of the site is considered to be low and, if present, is likely to be relatively shallow and date to the late prehistoric and/or Romano-British periods. The land has been in agricultural use since the medieval period.

- 5.66. The submitted geophysical survey suggested that the majority of anomalies highlighted relate to modern material and geological variations. Based on this information the Council's Archaeologist had recommended that a series of intrusive evaluations be undertaken prior to any development commencing on site.
- 5.67. In total 5 trenches were excavated. The aim of this trenching was to determine the presence or absence, nature, date and quality of survival and importance of archaeological deposits to enable an assessment of the potential and significance of the archaeology to be made. Four of the trenches measured 30m x 2m and a fifth trench was dug at the request of the Archaeologist. The location of the trenches was informed by the earlier geophysical survey of the site.
- 5.68. The archaeological evaluation has concluded an absence of significant archaeological finds and features on the site. Trenches 1 and 5 correspond with an anomaly identified in the geophysical survey. No archaeological material was recovered to aid the understanding of the site. The presence of plough furrows identified on the site suggest the land has been utilised for agricultural purposes since at least the medieval period.
- 5.69. The Archaeologist had originally requested that the investigation works and evaluation of those results be secured by condition in the event of granting planning permission. However, as the applicant has now undertaken these works and the outcome is satisfactory, the originally requested conditions are no longer necessary. The proposed development is therefore considered to accord Section 16 of the NPPF and policy D6 of the DLP 2018.

## **ECOLOGY**

- 5.70. Section 15 of the NPPF covers the conservation and enhancement of the natural environment. It states that planning policies and decisions should contribute to and enhance the natural and local environment; by minimising impacts upon on an providing net gains for biodiversity, including by establishing coherent ecological networks that are more resilient to current and future pressures. In the context of determining planning applications (Para 180, c)) states that 'opportunities to improve biodiversity in and around developments should be integrated as part of their design, especially where

this can secure measurable net gains for biodiversity or enhance public access to nature where this is appropriate. Policy GI2 of the emerging Local Plan also seeks to achieve similar objectives; with the overarching aim of conserving and enhancing York's biodiversity. Policy GI2 (iv) specifically requires development to result in a net gain to, and help improve, biodiversity.

- 5.71. Policy RwK 04 of the adopted Neighbourhood Plan states: *'Development proposals that conserve or enhance wildlife, wild flowers, hedgerows and trees will be supported'*.
- 5.72. The proposed development is to be located within the existing confines of the site. Much of the existing perimeter hedging is to be retained and only subjected to minor management and tidying works. Existing trees within and adjacent to the site are to be retained.
- 5.73. The submitted Preliminary Ecological Appraisal utilises a High, Moderate and Low classification criteria; each category then uses an inflection (+/-) to denote whether the feature has been assessed as being at the higher or lower end of that category. The assessment has concluded that the site is generally of Moderate (M-) classification with an area of Low (L+) in the northern field. The site has been predicated to show a Biodiversity Net Gain from M- to M as a result of the development. The assessment has also concluded that no further assessments or surveys are recommended, unless works to the surrounding hedgerows is planned during bird nesting season.
- 5.74. The survey has noted that the application site offers suitable habitat for nesting birds. Bats are also likely to use the site for foraging but are unlikely to find opportunities for roosting. No evidence of other species on site were detected.
- 5.75. The councils Ecologist has not raised any objections to the proposed development, subject to a series of conditions upon the granting of any planning permission. The recommended conditions relate to nesting birds, biodiversity enhancements and the submission of a lighting plan. Cumulatively these conditions will ensure that a precautionary approach during the construction phase ensuring existing species can be safeguarded. They will also secure enhancements which will co-exist with the development post construction.
- 5.76. Overall, the proposals would accord with the provisions of Section 15 of the NPPF and the proposals would achieve a Biodiversity Net Gain. The proposals would also accord with Policy GI2 of the DLP 2018 and Policy RwK

04 of the adopted neighbourhood plan. The potential risks to protected species and existing habitats can be suitably managed via a series of mitigation measures which can be secured by planning condition.

## **SUSTAINABLE DESIGN AND CONSTRUCTION**

- 5.77. Policy CC1 and CC2 of the DLP 2018 establish local requirements on sustainable construction. They require that, compared to Building Regulation targets, new buildings achieve a reduction in carbon emissions of at least 28% unless it can be demonstrated that this is not viable (CC1). At least 19% of such should be from building fabric efficiency (CC2). It should be noted that forthcoming changes to Building Regulations will impose more stringent reductions. As a result, depending upon the timing of the building works relative to prevailing Building Regulation requirements and any transitional arrangements, Building Regulations may impose measures that exceed the requirements of policies CC1 and CC2.
- 5.78. The provisions of Policy CC1 and CC2 have been noted within the Energy Statement that has been submitted with the application. The submitted Energy Statement also sets out a series of measures that the developer intends to implement as part of the development to ensure that the proposals accord with the provisions of CC1 and CC2. The measures set out within the Energy Statement cover two main areas; the fabric of the buildings to be built and the specification of any mechanical equipment to be utilised in the dwellings. The proposed measures include a focus upon the fabric specification of the dwelling units utilising materials with a low thermal conductivity rating, meaning that they do not conduct and therefore lose heat easily. In addition to this the Energy Statement indicates that the dwellings are to be heated using air source heat pumps and utilise energy efficient lighting throughout. Water efficient fixtures and fittings will also be used where they are fitted by the developer.
- 5.79. Combining these measures, according to the submitted Energy Statement, the development should achieve the carbon reduction requirements specified within policies CC1 and CC2.
- 5.80. Notwithstanding the above, the exact location and specification of the mechanical measures to be utilised have not been provided. It would be anticipated that the air source heat pumps would be positioned on the ground to the exterior of the building with sufficient space around them to allow for their efficient operation. Visually such units have a similar size and appearance to an air conditioning fan unit. In addition to this the calculations

provided within the Energy Statement will likely be formulated on the basis of the fabric of the building and the specification of the mechanical measures to be used achieving either a known and modelled reduction in emissions. Such calculations may be liable to change in the event of the specification of materials or equipment changing.

5.81. Therefore, whilst the submitted information indicates that the requirements of Policy CC1 and CC2 should be capable of being achieved, in order to ensure that this remains the case, but to also provide a degree of flexibility in terms of how that is achieved, it is considered necessary and appropriate to impose conditions which will require each dwelling to achieve a reduction in carbon emissions to a level that is stated within Policies CC1 and CC2.

## **PLANNING OBLIGATIONS**

### **Education**

5.82. Policy DM1 of the draft local plan states that the Council will seek financial contributions from developers to ensure that the necessary infrastructure is in place to support future development in York. In terms of education provision, the Council's supplementary planning guidance note sets out the methodology.

5.83. The need arising from the development and how this would be accommodated is as follows:

- Early Years – none requested, as there is no childcare within Rufforth or within 2 mile radius to expand. It is anticipated that places are available elsewhere chosen for proximity to work.
- Primary - £113,856 toward expansion and facilities at Rufforth Academy.
- Secondary - £78,378 toward Phase 1 expansion at Manor School.

### **Affordable Housing**

5.84. The proposed development would achieve an on-site the affordable housing provision of 28.57% (6 Units). In order to achieve the threshold of 30% affordable housing provision, the payment of a commuted sum would be necessary. The provision of these units and the required commuted sum, and the mechanisms and frameworks by which they are delivered and then transferred to an appointed registered provider, need to be secured within a Section 106 agreement.

## **Open Space**

- 5.85. All residential development proposals are expected to contribute to the provision of open space for recreation and amenity in line with Policy GI6. Each of the proposed dwellings would benefit from private amenity spaces. However, the proposals, in this case, do not propose any substantive open space within the development other than for general landscaping.
- 5.86. Due to the size of the site, on-site provision would be likely to prove problematic and in this case a financial contribution for off-site provision would be more appropriate. Based on the number of dwellings and number of bedrooms proposed the required contributions would total £33,940. This would be broken down as £7,097 toward amenity space, £16,832 toward play space and £10,011 toward sports provision. The contributions would support existing facilities and/or clubs in the village. The amenity and play space contributions would be distributed in consultation with the Parish Council.
- 5.87. With regard to the future ongoing maintenance of the land toward the south western side of the site which would not naturally fall within the ownership of the proposed plots, the applicant has stated that this could be carried out by a management company. This can also be secured through a Section 106 Agreement.

## **The case for very special circumstances**

- 5.88. The proposed residential development represents inappropriate development in the Green Belt. Paragraph 147 of the NPPF explains that inappropriate development is, by definition, harmful to the Green Belt and should not be approved except in very special circumstances. In addition, there is limited harm to the openness of the Green Belt. Paragraph 148 also says when considering any planning application, local planning authorities should ensure that substantial weight is given to any harm to the Green Belt. 'Very special circumstances will not exist unless the potential harm to the Green Belt by reason of inappropriateness and any other harm resulting from the proposal, is clearly outweighed by other considerations. The following considerations have been put forward to justify the proposal:

## **Draft Allocation**

- 5.89. The site is allocated for residential development within the Draft Local Plan and has been so since 2013. The Draft Local Plan has reached an advanced stage. The allocation of the site has been the subject of a limited number of
- Application Reference Number: 21/02661/FULM                      Item No: 4a

comments and the majority of issues raised have been overcome by the technical work undertaken to support this application. The site has therefore been long established as an appropriate site for residential development.

### **Neighbourhood Plan**

5.90. The site was identified as a suitable location for housing within the Neighbourhood Plan. However, this was not formally allocated in the 'made' version of the plan, owing to the fact that the Draft Local Plan had yet to be adopted and Green Belt boundaries established. However, there is a clear resolution in the appendices of the Neighbourhood Plan, confirming that the Neighbourhood Plan will be subject of a review following adoption of the draft local plan.

### **Unmet Housing Need**

5.91. At the present time, the Council cannot currently demonstrate an NPPF compliant 5 year housing supply on deliverable sites on land that is outside of the general extent of the Green Belt, i.e. the site allocations in the emerging Local Plan are required. This site is an allocated housing site in the emerging Local Plan.

5.92. The Council has concluded that changes to the general extent of the York Green Belt are required to meet the development needs for housing, employment land and education, which cannot be solely provided in urban areas or villages (outside of the Green Belt) or by other means. It is recognised that an undersupply of homes or employment land would exacerbate housing affordability issues, increase unsustainable commuting patterns and adversely impact on building a strong, competitive economy. The application site is proposed to be allocated to help meet the overall needs of the city within the general extent of the Green Belt following an extensive exercise to identify suitable sites which minimise harm on York's environmental assets and the purposes of the Green Belt.

### **Provision of Affordable Housing**

5.93. The proposals would give rise to a policy compliant level of affordable housing thus contributing to the delivery of affordable housing within the City of York Council area. This is a material consideration to which substantial weight can be attached.

### **Whether the site serves any of the five purposes of the Green Belt**

5.94. The five purposes of the Green Belt are set out at Paragraph 138 of the NPPF and these are:

- a) To check the unrestricted sprawl of large built up areas;
- b) To prevent neighbouring towns merging into one another;
- c) To assist in safeguarding the countryside from encroachment;
- d) To preserve the setting and special character of historic towns; and
- e) To assist in urban regeneration, by encouraging the recycling of derelict and other urban land.

5.95. The application site is a housing allocation within the emerging Local Plan (H38) which was defined as Green Belt in the 2005 DLP. Topic Paper 1: Approach to defining Green Belt Addendum 2021 provides detailed information about the York Green Belt and the emerging Local Plan, including an explanation of how and where detailed inner and outer Green Belt boundaries have been defined to inform the Local Plan. Criteria to inform the delineation of the detailed boundaries are set out within Section 5 of the Topic Paper and have been identified on the basis of consideration of national guidance, the strategic approach undertaken in the local plan core strategy and an appraisal of the essential characteristics of openness and permanence in York. The detailed boundaries have then been assessed in the context of the existing built environment and landscape, without taking account of the potential need for growth and expansion of the built up area and settlements. Annexes 2, 3 and 4 present the potential boundary to the Green Belt should there be no unmet identified need.

5.96. The addendum sets out a methodology based on a local definition of openness and permanence and evidence which describes the purposes of land within the Green Belt, which is used to define the detailed Green Belt boundary. The key role of the boundary is to establish long term development limits to the built up area and existing settlements, and distinguish land that needs to be kept permanently open to meet the purposes of Green Belt including safeguarding the special character and setting of the historic city.

5.97. The main element of the appraisal of the location of Green Belt boundaries around the village of Rufforth is set out in Annex 4 (Other densely developed Areas in the General Extent of the Green Belt) to the addendum. A total of 4 boundaries are identified around the village. Boundary 1 runs along northern and eastern side of the village and includes the land that forms the subject of this application.

- 5.98. Allowing the village to grow significantly would result in it becoming out of proportion with the settlement pattern of York, an important feature identified in the Heritage Topic Paper. Increasing the distance of residential areas away from the village core can cause harm to the compactness of the village. Rufforth is typical of York's outlying linear villages, surrounded by mostly flat, open, agricultural land with many large fields. While there has been some ribbon development to the north and south beyond the original village core, development tends to have infilled rather than extended beyond Main Street. Small housing development in farmyards and paddocks, once adjacent to the road, have created a number of cul-de-sacs.
- 5.99. It is considered that the form and character of Rufforth offers an opportunity, via a modest expansion of the village, for focusing development towards built up areas within the Green Belt in order to contribute to the long term permanence of the York Green Belt.
- 5.100. Whilst a number of proposed sites in and around the existing village were put forward as part of the Local Plan process, only the application site was included in the Local Plan as a housing allocation. This was determined as the most appropriate location for development in the village as it would follow a combination of historic field boundaries and more recent 20<sup>th</sup> century development boundaries of properties off Wetherby Road, or small groups of properties and cul-de-sacs. The new boundary offers a degree of permanence. The development is located to the north side of the village minimising the perception of development from open approaches.
- 5.101. The site selection process and Topic Paper 1 Approach to defining York's Green Belt addendum 2021 have informed the housing allocations in the 2018 DLP. It has been determined that this site, due to its performance against Green Belt purposes specific to York, the spatial strategy for sustainable growth and taking into account NPPF policy on setting Green Belt boundaries can be within the Rufforth settlement and excluded from the Green Belt.
- 5.102. The proposed development would be inappropriate development in the Green Belt and it would lead to limited harm in respect to openness. The adverse effect Green Belt is significantly less than site ST31 (land at Tadcaster Road, Copmanthorpe) which was considered at Planning Committee A 11 July 2022 and where very special circumstances were determined to exist. Even when substantial weight is attached to the harm to the Green Belt, cumulatively there are considerations which clearly outweigh



the potential harm to the Green Belt and any other harm as a result of development so as to amount to the very special circumstances which are required by the NPPF.

- The existing village is a densely developed area which exhibits a low degree of openness, and does not contribute to the openness of the Green Belt; as a result Rufforth is therefore inset within the Green Belt.
- Unmet housing need cannot be accommodated on deliverable sites on land that is outside of the general extent of Green Belt. Given the location of the site at the edge of an existing settlement the site is sustainably located.
- Aside from the issue of Green Belt there are no objections to the scheme considering other material considerations which cannot be addressed through either planning conditions or S106 agreement.
- Overall the application would represent sustainable development that will conform to the Government's objective of significantly boosting the supply of homes.

5.103. Policy SS2 of the Draft Local Plan sets out the role of the York Green Belt. The boundary of the Green Belt is the consequence of decisions taken about which land serves a Green Belt purpose and which can be allocated for development. The Plan seeks to identify sufficient land to accommodate York's development needs across the plan period. In addition, it provides additional development land to 2038 beyond the plan period, the purpose of which is to ensure that in defining the boundaries of the Green Belt they can then endure and support the prime purpose of the Green Belt of preserving the setting and special character of York.

### **Whether prematurity is grounds to refuse the application**

5.104. Paragraph 49 of the NPPF states that "in the context of the Framework – and in particular the presumption in favour of sustainable development – arguments that an application is premature are unlikely to justify a refusal of planning permission other than in the limited circumstances where:

- a) The development proposed is so substantial, or its cumulative effect would be so significant, that to grant permission would undermine the plan-making process by predetermining decisions about the scale, location, or phasing of new development that are central to the emerging plan; and
- b) The emerging plan is at an advanced stage but is not yet formally part of the development plan for the area".

5.105. Paragraph 50 of the NPPF states: “Refusal of planning permission on the grounds of prematurity will seldom be justified where a draft local plan has yet to be submitted for examination; or – in the case of a neighbourhood plan – before the end of the local planning authority publicity period on the draft plan. Where planning permission is refused on the grounds of prematurity, the local planning authority will need to indicate clearly how granting permission for the development concerned would prejudice the outcome of the plan making process”.

5.106. It is considered that to grant planning permission for this scheme would not undermine the plan-making process because the Council’s assessment of the Green Belt to inform the emerging plan (as detailed within Topic Paper 1: Approach to defining the Green Belt Addendum 2021) concluded that the site can accommodate development without harm to the Green Belt purposes specific to York. Given the scale of the development proposed (21 dwellings) as the emerging Local Plan has been submitted for examination and promotes this as a housing site, to be delivered within the short term (1-5 years) of the plan, there are no clear grounds (as is required by the NPPF) to refuse this particular application on the basis that it would prejudice the plan-making process.

5.107. There are outstanding objections to the removal of land from the general extent of the Green Belt and the delineation for Green Belt boundaries. Such objections reduce the weight that can be attributed to the emerging plan. However, even taking this into account and recognising that it is a matter of planning judgement it is considered that there are very special circumstances as set out in paragraph 5.103 which justify the development at this particular time. Also of note is that the site was put forward as a potential development site as part of the Neighbourhood Plan process. However, this was ultimately removed from the NHP as the identification and modification of Green Belt boundaries, and by extension the allocation of housing sites, are matters for the local planning authority via the Local Plan process rather than through the Neighbourhood Plan.

## **6.0 CONCLUSION**

6.1 The above report outlines that the proposed development, subject to conditions, would be compliant with the NPPF and relevant technical policies within the adopted Neighbourhood Plan and 2018 Draft Local Plan with regard to the impact on the highway network, residential amenity, archaeology, biodiversity, flood risk and drainage. In addition to this there are considered to be suitable mechanisms to ensure that the infrastructure required to support the development can be secured.

6.2 At present the site is considered to remain within the general extent of the Green Belt. However, the site is allocated for housing development in the 2018 DLP. It has been determined the site, due to its performance against Green Belt purposes specific to York, the spatial strategy for sustainable growth and taking into account NPPF policy on setting Green Belt boundaries can be within the Rufforth settlement and not in the Green Belt. It is considered that there are very special circumstances that cumulatively clearly outweigh the potential harm to the Green Belt by reason of inappropriateness and the limited adverse impact on the openness of the Green Belt and any other harms, even when giving substantial weight to the Green Belt harms. Further, there is no case for refusing the scheme on prematurity grounds.

6.3 Based on the merits of this case it is recommended that planning permission be granted subject to conditions and completion of a Section 106 Agreement.

## **7.0 RECOMMENDATION:**

### **Approve subject to Section 106 Agreement**

7.1 Delegated authority be given to the Head of Planning and Development Services to APPROVE the application subject to the planning obligations and conditions set out below, and The Head of Planning and Development Services be given delegated authority to finalise the terms and details of the Section 106 obligations and conditions.

#### Section 106 Planning Obligation to secure:

- Education Contributions
- Affordable Housing Provision
- Open Space contributions and ongoing Management of open space within the site

#### Planning conditions

1 TIME2 Development start within three years

2 The development hereby permitted shall be carried out in accordance with the following plans and other submitted details:-

Site Layout Plan: Drawing No. 3921/PD/100 Revision J;

Proposed Levels and FFLs: Drawing No. 4001 Rev P2;

Landscape Plan Titled Hawthorn Fields, Rufforth: Drawing No. 3809/1;

Outline Landscape Proposals: Drawing No. 3809/3 Rev B;

H4 Terrace Plans: Panning Drawing Plots 1,2 and 3: Drawing No. 3921-PD-01 Rev

Application Reference Number: 21/02661/FULM Item No: 4a

A;  
H4 Terrace Elevations: Planning Drawing Plots 1,2 and 3: Drawing No. 3921-PD-02 Rev A;  
A3 Semi Plans: Planning Drawing Plots 8 and 9 Drawing No. 3921-PD-03 Rev B;  
A3 Semi Elevations: Planning Drawing Plots 8 and 9 Drawing No.3921-PD-04 Rev B;  
Ashby and Hawthorn Semi: Planning Drawing (as) Plots 15 and 16 Drawing No. 3921-PD-05 Rev A;  
Ashby and Hawthorn Sem: Planning Drawing (op) Plots 17 and 18 Drawing No. 3921-PD-06 Rev A;  
Newton: Planning Drawing (as) Plot 6 Drawing No. 3921-PD-07 Rev A;  
Newton Planning Drawing (op) Plot 13 Drawing No. 3921-PD-08 Rev A;  
Newton plus attached garage: Planning Drawing (as) Plot 10 Drawing No. 3921-PD-09 Rev A;  
Ashby semi: Planning Drawing Plots 4-5 Drawing No. 3921-PD-10 Rev A;  
Banbury: Planning Drawing (as) Plot 11 Drawing No. 3921-PD-11 Rev A;  
TLB Barn: Planning Drawing (as) Plot 19 Drawing No. 3921-PD-13 Rev A;  
TCB Barn Floor Plans: Planning Drawing (as) Plot 20 Drawing No. 3921-PD-14 Rev B;  
TCB Barn Elevations and Sections Planning Drawing (as) Plot 20 Drawing No. 3921-PD-15 Rev A;  
TCB Barn Floor Plans: Planning Drawing (op) Plot 21 Drawing No. 3921-PD-16 Rev B;  
TCB Barn Elevations and Sections: Planning Drawing (op) Drawing No. 3921-PD-17 Rev A;  
Chilton (corner hipped): Planning Drawing (as) Plot 12 Drawing No. 3921-PD-18 Rev A;  
Garage: Planning Drawing (as) Plots 6,11,12,13 and 14 Drawing No. 3921-PD-19 Rev A;  
Streetscenes: Drawing No. 3921-PD-20 Rev C;  
Farnham Type: Planning Drawing (as) Plots 7 Drawing No. 3921-PD-22 Rev A;  
Farnham Type: Planning Drawing (as) Plot 14 Drawing No. 3921-PD-23;

Reason: For the avoidance of doubt and to ensure that the development is carried out only as approved by the Local Planning Authority.

3 Notwithstanding the details submitted, prior to commencement of the development a Construction Environment Management Plan (CEMP) for minimising the creation of noise, vibration and dust during the demolition, site preparation and construction phases of the development shall be submitted to and approved in writing by the Local Planning Authority. The CEMP must include a site-specific risk assessment of dust impacts in line with the guidance provided by IAQM (see <http://iaqm.co.uk/guidance/>) and include a package of mitigation measures commensurate with the risk identified in the assessment. All works on site shall be undertaken in accordance with the approved CEMP, unless otherwise first agreed in

writing by the Local Planning Authority.

Reason: To protect the amenity of the locality in accordance with Policy ENV2 of the Draft Local Plan 2018

NOTE: For noise details on hours of construction, deliveries, types of machinery to be used, use of quieter/silenced machinery, use of acoustic barriers, prefabrication off site etc, should be detailed within the CEMP. Where particularly noisy activities are expected to take place then details should be provided on how they intend to lessen the impact i.e. by limiting especially noisy events to no more than 2 hours in duration. Details of any monitoring may also be required, in certain situation, including the location of positions, recording of results and identification of mitigation measures required.

For vibration details should be provided on any activities which may results in excessive vibration, e.g., piling, and details of monitoring to be carried out. Locations of monitoring positions should also be provided along with details of standards used for determining the acceptability of any vibration undertaken. In the event that excess vibration occurs then details should be provided on how the developer will deal with this, i.e., substitution of driven pile foundations with auger pile foundations. Ideally all monitoring results should be recorded and include what was found and mitigation measures employed (if any).

With respect to dust mitigation, measures may include, but would not be restricted to, on site wheel washing, restrictions on use of unmade roads, agreement on the routes to be used by construction traffic, restriction of stockpile size (also covering or spraying them to reduce possible dust), targeting sweeping of roads, minimisation of evaporative emissions and prompt clean-up of liquid spills, prohibition of intentional on-site fires and avoidance of accidental ones, control of construction equipment emissions and proactive monitoring of dust. Further information on suitable measures can be found in the dust guidance note produced by the Institute of Air Quality Management, see <http://iaqm.co.uk/guidance/>. The CEMP must include a site-specific risk assessment of dust impacts in line with the IAQM guidance note and include mitigation commensurate with the scale of the risks identified.

For lighting details should be provided on artificial lighting to be provided on site, along with details of measures which will be used to minimise impact, such as restrictions in hours of operation, location and angling of lighting.

In addition to the above the CEMP should provide a complaints procedure, so that in the event of any complaint from a member of the public about noise, dust, vibration or lighting the site manager has a clear understanding of how to respond to complaints received. The procedure should detail how a contact number will be advertised to the public, what will happen once a complaint had been received (i.e., investigation), any monitoring to be carried out, how they intend to update the

complainant, and what will happen in the event that the complaint is not resolved. Written records of any complaints received, and actions taken should be kept and details forwarded to the Local Authority every month during construction works by email to the following addresses [public.protection@york.gov.uk](mailto:public.protection@york.gov.uk) and [planning.enforcement@york.gov.uk](mailto:planning.enforcement@york.gov.uk)

4 Prior to the commencement of development, details of the proposed means of foul and surface water drainage, including details of any balancing works and off site works, shall be submitted to and approved in writing by the Local Planning Authority. The development shall be carried out in accordance with the approved details.

Design considerations.

The developer's attention is drawn to Requirement H3 of the Building Regulations 2000 with regards to hierarchy for surface water dispersal and the use of Sustainable Drainage Systems (SuDS). Consideration should be given to discharge to soakaway, infiltration system and watercourse in that priority order. Surface water discharge to the existing public sewer network must only be as a last resort therefore sufficient evidence should be provided i.e. witnessed by CYC infiltration tests to BRE Digest 365 to discount the use of SuDS.

As SuDS methods have been proven to be unsuitable then a suitable watercourse must be considered in accordance with the following criteria; In accordance with City of York Councils City of York Councils Sustainable Drainage Systems Guidance for Developers (August 2018) and in agreement with the Environment Agency and the York Consortium of Internal Drainage Boards, peak run-off from Brownfield developments must be attenuated to 70% of the existing rate (based on 140 l/s/ha of proven by way of CCTV drainage survey connected impermeable areas during the 1 in 1 year event). Storage volume calculations, using computer modelling, must accommodate a 1:30 year storm with no surface flooding, along with no internal flooding of buildings or surface run-off from the site in a 1:100 year storm. Proposed areas within the model must also include an additional 30% allowance for climate change. The modelling must use a range of storm durations, with both summer and winter profiles, to find the worst-case volume required.

As there are no existing connected impermeable areas this Greenfield site must be limited to the pre-development run off rate. The pre-development run off rate should be calculated using either IOH 124 or FEH methods (depending on catchment size) during a 1 in 1 year event. Please be advised as the watercourse appears to be nearby and any discharge will be new/additional therefore only the proposed developed areas (i.e. hard paving and roof areas) can be used to calculate this rate. It is recommend discussing and agreeing the permitted discharge rate with the Councils Flood Risk Management Team at an early stage.

The applicant should provide a topographical survey showing the existing and proposed ground and finished floor levels to ordnance datum for the site and

adjacent properties. The development should not be raised above the level of the adjacent land, to prevent runoff from the site affecting nearby properties.

Details of the future management and maintenance of the proposed drainage scheme must be provided.

Reason: So that the Local Planning Authority may be satisfied with these details for the proper and sustainable drainage of the site.

5 The development hereby permitted shall achieve a reduction in carbon emissions of at least 28% compared to the target emission rate as required under Part L of the Building Regulations. Prior to the commencement of development above slab level details of the measures undertaken to secure compliance with this condition shall be submitted to and approved in writing by the local planning authority. The development shall be carried out in accordance with the approved details.

Reason: To fulfil the environmental objectives of the National Planning Policy Framework (NPPF) and support the transition to a low carbon future, and in accordance with policies CC1 and CC2 of the Publication Draft Local Plan 2018

6 A biodiversity enhancement plan/drawing shall be submitted to, and be approved in writing by, the local planning authority prior to the commencement of development. The plan should include a minimum of six bat boxes, suitable for crevice dwelling species and six boxes for nesting birds. The measures contained in the approved plan shall be implemented in accordance with the approved details prior to first occupation of the relevant building.

Reason: To take account of and enhance the biodiversity and wildlife interest of the area, and to be in accordance with Paragraph 174 d) of the NPPF (2021) to contribute to and enhance the natural and local environment by minimising impacts on and providing net gains for biodiversity, including establishing coherent ecological networks that are more resilient to current and future pressures.

7 Vehicular access shall be from Middlewood Close and details of the design of this access, together with associated sight lines, shall be submitted to and approved in writing by the Local Planning Authority prior to the commencement of the development. The development shall be carried out in accordance with the approved details.

Reason: In the interests of highway safety.

8 HWAY10 Vehicular areas surfaced, details reqd

9 HWAY18 Cycle parking details to be agreed

10 HWAY19 Car and cycle parking laid out

11 The development shall not commence until details of the internal road layout including any areas to be put forward for adoption by the Local Highway Authority have been submitted to, and approved in writing, by the Local Planning Authority. No building/dwelling shall be occupied until the internal road has been provided, up to base-course level, in accordance with such approved plans. The wearing course shall be laid within two years of the base-course being laid or prior to the occupation of the penultimate house, whichever is the sooner.

Reason: In the interests of road safety.

12 Prior to the commencement of development a detailed method of works statement identifying the programming and management of site clearance/preparatory and construction works shall be submitted to and approved in writing. The statement shall include at least the following information;

- measures to prevent the egress of mud and other detritus onto the adjacent public highway
- a dilapidation survey jointly undertaken with the local highway authority
- the routing for construction traffic that will be promoted
- a scheme for signing the promoted construction traffic routing
- the management of construction traffic and contractor parking
- hours of operation (including deliveries) which must include a statement indicating that deliveries to and from the site will take place outside of school drop-off/pick up times.
- where materials are to be stored within the site

The measures set out in the statement as approved shall be implemented at all times during the clearance/preparatory and construction works of the development.

Reason: To ensure that the development can be carried out in a manner that will not be to the detriment of amenity of local residents, free flow of traffic or safety of highway users.

13 In the event that unexpected contamination is found at any time when carrying out the approved development, it must be reported in writing immediately to the Local Planning Authority. An investigation and risk assessment must be undertaken and, if remediation is necessary, a remediation strategy must be prepared, which is subject to approval in writing by the Local Planning Authority. Following completion of measures identified in the approved remediation strategy, a verification report must be submitted to and approved by the Local Planning Authority. It is strongly recommended that all reports are prepared by a suitably qualified and competent person.



Reason: To ensure that the site is suitable for its proposed use taking account of ground conditions and any risks arising from land contamination and to accord with Policy ENV2 of the Draft Local Plan 2018 and Section 15 of the National Planning Policy Framework

14 Notwithstanding any proposed materials specified on the approved drawings or in the application form submitted with the application, samples of the external materials to be used shall be submitted to and approved in writing by the Local Planning Authority prior to their use in the development. The development shall be carried out using the approved materials.

Note: Because of limited storage space at our offices it would be appreciated if sample materials could be made available for inspection at the site. Please make it clear in your approval of details application when the materials will be available for inspection and where they are located.

Reason: So as to achieve a visually cohesive appearance.

15 No tree works or vegetation clearance shall take place between 1st March and 31st August inclusive, unless a competent ecologist has undertaken a careful, detailed check of suitable habitat for active birds' nests immediately before the works and provided written confirmation that no birds will be harmed and/or that there are appropriate measures in place to protect nesting bird interest on site. Any such written confirmation should be submitted to the local planning authority.

Reason: To ensure that breeding birds are protected from harm during construction. All British birds, their nests and eggs (with certain limited exceptions) are protected by Section 1 of the Wildlife and Countryside Act 1981, as amended.

16 All demolition, construction works and ancillary operations, including deliveries to and dispatch from the site shall be confined to the following hours:

Monday to Friday 0800 to 1800 hours  
Saturdays 0900 to 1300 hours  
Not at all on Sundays and Bank Holidays

Reason: To protect the residential amenity of neighbouring residents in accordance with Policy ENV2 of the Draft Local Plan 2018.

17 Prior to the installation of any new external lighting, a 'lighting design plan' shall be submitted to and approved in writing by the local planning authority. Any external lighting shall be installed in accordance with the approved lighting design plan.

Details of the height, type, position, angle and spread of any external lighting shall be submitted to and approved in writing by the Local Planning Authority. The approved scheme shall be installed and operational prior to the development hereby permitted being brought into use. The external lighting shall be erected and maintained in accordance with the approved details to minimise light spillage and glare outside the designated area.

Reason: To maintain the favourable conservation status of protected species. To protect residential amenity. To protect visual amenity and character of the area

18 All Electric Vehicle Charging Points shall incorporate a suitably rated 32A electrical socket (minimum) to allow 'Mode 3' charging of an electric vehicle. The exact specification (make/model) of all Electric Vehicle Recharging Points (both in-curtilage charge points and remote charge points) shall be agreed in writing by the Local Planning Authority prior to occupation.

Reason: To promote and facilitate the uptake of electric vehicles on the site in line with the Council's Low Emission Strategy (LES) and the Paragraph 112 of the National Planning Policy Framework (NPPF).

19 Unless otherwise approved in writing by the local planning authority, there shall be no piped discharge of surface water from the development prior to the completion of the approved surface water drainage works and no buildings shall be occupied or brought into use prior to completion of the approved foul drainage works.

Reason: So that the Local Planning Authority may be satisfied that no foul and surface water discharges take place until proper provision has been made for their disposal.

20 The site shall be developed with separate systems of drainage for foul and surface water on and off site.

Reason: In the interests of satisfactory and sustainable drainage

21 Existing trees shown as retained on the approved plans shall be protected in accordance with BS: 5837: 'Trees in relation to construction'.

Reason: In accordance with paragraph 55 of the NPPF, to ensure protection of existing trees that make a significant contribution to the amenity of the area and to biodiversity and are fundamental to whether the scheme would be acceptable when assessed against policies within the NPPF.

22 The approved landscaping scheme, as shown on drawing Hawthorn Fields, Rufforth (Drawing No. 3809/1) shall be implemented no later than 6 months of the

practical completion of the last dwelling. Any trees or plants which within 5 years of planting die, are removed or become seriously damaged or diseased in the opinion of the Local Authority shall be replaced in the next planting season with others of a similar size and species.

Reason: In the interests of amenity and good design and to afford suitable time for the landscaping scheme to established itself in the development.

## **8.0 INFORMATIVES:**

### **Notes to Applicant**

#### **1. STATEMENT OF THE COUNCIL`S POSITIVE AND PROACTIVE APPROACH**

In considering the application, the Local Planning Authority has implemented the requirements set out within the National Planning Policy Framework (paragraph 38) in seeking solutions to problems identified during the processing of the application. The Local Planning Authority took the following steps in order to achieve a positive outcome:

Amendments have been sought and secured which addressed concerns in relation to housing mix, landscaping and tree protection measures and parking provision.

#### **2. HEDGEHOGS**

As noted in section 7.30 of the PEA, the application site offers suitable habitat for hedgehogs. The applicant is advised to consider using permeable fencing or leaving occasional gaps suitable to allow passage of hedgehogs. Any potential hibernation sites including log piles should be removed outside the hibernation period (which is between November and March inclusive) in order to avoid killing or injuring hedgehog. Hedgehogs are of priority conservation concern and are a Species of Principal Importance under section 41 of the NERC Act (2006). An important factor in their recent population decline is that fencing and walls are becoming more secure, reducing their movements and the amount of land available to them. Small gaps of approximately 13x13cm can be left at the base of fencing to allow hedgehogs to pass through. Habitat enhancement for hedgehogs can easily be incorporated into developments, for example through provision of purpose-built hedgehog shelters or log piles.

<https://www.britishhedgehogs.org.uk/wp-content/uploads/2019/05/developers-1.pdf>

#### **3. WILDLIFE AND COUNTRYSIDE ACT**

The applicant is reminded that, under the Wildlife and Countryside Act1981, as amended (section 1), it is an offence to remove, damage or destroy the nest of any


wild bird while that nest is in use or being built. Planning consent for a development does not provide a defence against prosecution under this act. Buildings, trees and scrub are likely to contain nesting birds between 1st March and 31st August inclusive. Suitable nesting habitat is present on the application site and is to be assumed to contain nesting birds between the above dates, unless a recent survey has been undertaken by a competent ecologist to assess the nesting bird activity on site during this period and has shown it is absolutely certain that nesting birds are not present.

**Contact details:**

**Case Officer:** Mark Baldry  
**Tel No:** 01904 552877

# Land To The East Of Middlewood Close, Rufforth

21/02661/FULM



Scale : 1:1602

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationery Office © Crown Copyright 2000.

Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings.

<b>Organisation</b>	City of York Council
<b>Department</b>	Directorate of Place
<b>Comments</b>	Site Location Plans
<b>Date</b>	03 August 2022
<b>SLA Number</b>	Not Set

This page is intentionally left blank



# Planning Committee B

To be held on Thursday 11<sup>th</sup> August 2022 at 4:30pm

# 21/02661/FULM – Land to the east of Middlewood Close, Rufforth

Erection of 21 dwellings and associated works





YOUR OBLIGATION TO THE CLIENT DOES NOT EXCLUDE THE OBLIGATION TO THE PUBLIC. THE CLIENT'S OBLIGATION TO THE PUBLIC IS NOT EXCLUDED BY THIS DRAWING. A CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITY AND OTHER RELEVANT AGENCIES. THE CLIENT SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITY AND OTHER RELEVANT AGENCIES. THE CLIENT SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITY AND OTHER RELEVANT AGENCIES.

REV	DATE	DESCRIPTION
A	19/01/22	STREET & HOUSE LIGHT POSITIONS ADDED
B	22/01/22	REVISION AMENDS PL 18 DETACHED 4 BED GAS TANKS REMOVED
C	26/03/22	FINISHED FLOOR LEVELS ADDED
D	11/03/22	REVISIONS TO ACCOMMODATE PUMP STATION
E	23/04/22	FFLS ADDED
F	06/09/22	FURTHER HIGHWAY AMENDMENTS
G	02/10/22	FURTHER HIGHWAY AMENDMENTS, INCL. CYCLE STORE, B&S & ACCESS REFINEMENTS, ROAD TYPING, CLARIFIED V&S BAYS PARALLEL 2 BED PARKING BLOCKS, PL 19 HOUSE-SPECIFIC MODEL B&S COLLECTION POINTS ADDED




















Stoness | Ingworth Partnership | Ltd  
 chartered architects  
 info@architects.co.uk  
 +44 (0)1462 320700  
 24 Market Place  
 Rufforth, YO17 1JW  
 www.architects.co.uk


CLIENT  
  
**MULGRAVE**  
 PROPERTIES

PROJECT  
 Hawthorn Fields  
 Rufforth

DRAWING TITLE  
 Site Layout Plan  
 Planning Layout

ACCOMMODATION			
Affordable			Area sq ft
H4	2 bed house	3 no	781
A5	3 bed house	2 no	928
Farrham	4 bed house	1 no	1141
<b>Private</b>			
Hawthorn	2 bed house	2 no	695
Newton	3 bed house	3 no	1006
Ashby	3 bed house	4 no	878
Banbury	3 bed house	1 no	1188
Farrham	4 bed house	1 no	1141
T1 Barn	4 bed house	1 no	2038
TC Barn	4 bed house	2 no	2580
Chatsworth	4 bed house	1 no	1486
<b>TOTAL</b>		<b>21 no</b>	<b>24,193 sq ft</b>

- KEY**
-  PRIVATE DRIVE
  -  BLOCK PAVING
  -  EXISTING TREE RETAINED & ROOF PROTECTION
  -  INDICATIVE TREES AND HEDGE / SHRUBS (refer to landscape layout for full details)
  -  EXISTING TREE REMOVED
  -  0.45M HIGH KNEE RAIL
  -  1.8M HIGH SCREEN FENCE (with gaps for hedge/gate)
  -  1.2M HIGH ESTATE RAILINGS
  -  1.8M HIGH SCREEN WALL & PIER
  -  EXISTING TRACK RETAINED
  -  AFFORDABLE HOUSING - RENT
  -  AFFORDABLE HOUSING - SHARED
  -  REMOTE ELECTRIC CAR CHARGING POINT - COMBINED CHARGER + BOLLARD LIGHT
  -  ELECTRIC CAR CHARGING POINT
  -  BCP
  -  EXTERNAL WALL LIGHT TO FRONT & REAR
  -  PERSONNEL DOORS (Hspec HS LED)
  -  CYCLE STORE (2m x 1.4m)
  -  DENOTES FINISHED FLOOR LEVEL




Site Plan


**CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2015**

IN ORDER TO UNDERSTAND YOUR LEGAL OBLIGATIONS AS A CLIENT UNDER THE CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2015 (CDM 2015) PLEASE REFER TO THE HEALTH & SAFETY EXECUTIVE WEBSITE AT [www.hse.gov.uk/construction/](http://www.hse.gov.uk/construction/) OR CONTACT THE HSE FOR FURTHER INFORMATION.



YOUR DUTIES UNDER CDM 2015 INCLUDE (BUT ARE NOT LIMITED TO) IDENTIFYING THE RIGHT PEOPLE AT THE RIGHT TIME, MAKING APPROPRIATE TIME, MANAGING & ORGANISING THE PROJECT, ALLOWING ADEQUATE TIME, PROVIDING INFORMATION TO A COMMUNITY CONSULTATION (YOUR DESIGNER & CONTRACTORS), IDENTIFYING ADEQUATE WELFARE FACILITIES ON SITE, IDENTIFYING A COMMUNITY CONSULTATION PLAN IN PLACE, IDENTIFYING THE HEALTH & SAFETY PLAN, PROTECTING MEMBERS OF THE PUBLIC, INCLUDING YOUR EMPLOYEES, AND WORKING SAFELY AND CORRECTLY & NOTIFYING THE USE OF THE PROJECT IF APPLICABLE.



Section A - A



Section B - B




Key Plan (NTS)

ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.


Streetscenes




Front Elevation



Side Elevation



Rear Elevation




Side Elevation


Plots 1-3

**CONSTRUCTION (DESIGN & MANAGE)  
REGULATIONS 2015**


IN ORDER TO UNDERSTAND YOUR LEGAL OBLIGATIONS AS A CLIENT UNDER THE CONSTRUCTION (DESIGN & MANAGE) REGULATIONS 2015, PLEASE REFER TO THE HEALTH & SAFETY EXECUTIVES WEBSITE: <http://www.hse.gov.uk/oshsc15/cdm15/> OR CONTACT THE OFFICE FOR FURTHER INFORMATION. YOUR DUTIES UNDER CDM 2015 INCLUDE IDENTIFYING AND APPOINTING THE RIGHT PEOPLE AT THE RIGHT TIME, ENSURING ARRANGEMENTS FOR MANAGING & ORGANISING THE PROJECT, ALLOWING ADEQUATE TIME FOR DESIGN & CONSTRUCTION, ENSURING ADEQUATE WELLFARE FACILITIES ON SITE, ENSURING CONSTRUCTION PHASE PLANS ARE IN PLACE, NOTIFYING THE HEALTH & SAFETY PLAN, PROTECTING MEMBERS OF THE PUBLIC INCLUDING YOUR EMPLOYEES, ENSURING WORKPLACES ARE DESIGNED CORRECTLY & NOTIFYING THE USE OF THE PROJECT IF APPLICABLE.




FRONT




SIDE




SIDE



GROUND FLOOR



FIRST FLOOR



REAR


Plot 11









FRONT ELEVATION




REAR ELEVATION




SIDE ELEVATION



GROUND FLOOR PLAN



FIRST FLOOR PLAN




SIDE ELEVATION


CONSTRUCTION (DESIGN & MANAGEMENT)  
REGULATIONS 2015

IN ORDER TO UNDERSTAND YOUR LEGAL OBLIGATIONS AS A CLIENT UNDER  
THE CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2015 (CDM  
2015) PLEASE REFER TO THE HEALTH & SAFETY REGULATIONS WEBSITE AT  
<http://www.hse.gov.uk/construction/>


Plots 15 & 16




FIRST FLOOR




GROUND FLOOR




SIDE



SIDE



FRONT




REAR

ADAPTED FROM MULGRAVE PROPERTIES HOUSE TYPE - CDM 2015 REGULATIONS APPLY


**CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2015**

IN ORDER TO UNDERSTAND YOUR LEGAL OBLIGATIONS AS A CLIENT UNDER THE CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2015 (CDM 2015) PLEASE REFER TO THE HEALTH & SAFETY EXECUTIVE WEBSITE AT <http://www.hse.gov.uk/construction/> OR CONTACT THE OFFICE FOR SAFETY INFORMATION. YOUR DUTIES UNDER CDM 2015 INCLUDE (NOT EXHAUSTIVE LIST): APPOINTING THE RIGHT PEOPLE AT THE RIGHT TIME; ENSURING ARRANGEMENTS FOR MANAGING & ORGANISING THE PROJECT; ALLOWING SUFFICIENT TIME; PROVIDING INFORMATION TO & COMMUNICATION WITH YOUR DESIGNER(S) & CONTRACTOR(S); SHARING ASSESSMENT & RISK ASSESSMENT; ENSURING A CONSTRUCTION PHASE PLAN IS IN PLACE; HAVING THE HEALTH & SAFETY PLAN; PROTECTING MEMBERS OF THE PUBLIC; INCLUDING YOUR EMPLOYEES; ENSURING WORKSPACES ARE DESIGNED CORRECTLY & NOTIFYING THE USE OF THE PROJECT IF APPLICABLE.







FRONT



SIDE



REAR



SIDE



Plot 20



**COMMITTEE REPORT**

**Date:** 11 August 2022      **Ward:** Dringhouses And Woodthorpe  
**Team:** West Area      **Parish:** Dringhouses/Woodthorpe Planning Panel

**Reference:** 22/00872/FUL  
**Application at:** 29 Moor Lane Acomb York YO24 2QX  
**For:** Single storey side and rear extensions after demolition of existing garage, and loft conversion with hip to gable roof, dormer to rear and 2no. rooflights to front (part retrospective)  
**By:** Mr Roy Grant  
**Application Type:** Full Application  
**Target Date:** 15 August 2022  
**Recommendation:** Householder Approval

**1.0 PROPOSAL**

1.1 This application seeks planning permission for single storey side and rear extensions after the demolition of the existing garage, and a loft conversion with hip to gable roof extension, dormer to rear and 2no. roof-lights to the front. The site lies within the general extent of the Green Belt.

1.2 Amendments have been made to the scheme. The dormer reduced in width and the side extension reduced in length (at the side of the property). Matching windows are also proposed to the front and side of the dwelling so to be more sympathetic to the host dwelling and street.

1.3 The applicant has started works to the roof and therefore the application is now part retrospective.

1.4 The application is brought to Planning Committee, in accordance with the scheme of delegation, as the applicant is a chief officer / senior manager within the Council.

**2.0 POLICY CONTEXT**

Development Control Local Plan 2005

CYGP1 - Design

CYH7 - Residential extensions

CYGB1 - Development in Green Belt  
CYGB4 - Extensions to Existing Dwellings

Publication Draft Local Plan 2018

D1 - Placemaking

D11 - Extensions and Alterations to Existing Buildings

GB1 - Development in the Green Belt

### **3.0 CONSULTATIONS**

Dringhouses/Woodthorpe Planning Panel

3.1 Dringhouses/Woodthorpe Planning Panel object to the application on the grounds that the proposed works alter the aesthetics of the building and are out of character with the adjoining bungalows. They also feel the neighbours have justified concerns regarding being overlooked. They add that the applicant is an employee of the council, but the application form does not state this.

### **4.0 REPRESENTATIONS**

4.1 The occupants of No.25, 27 and 31 Moor Lane have objected to the application on the following grounds -

- The rear dormer results in loss of privacy.
- The works will lead to overshadowing and loss of light.
- Increase in noise with the addition of two additional bedrooms and an office.
- The extension is out of scale with the host dwelling and the works on a whole are considered to be an overdevelopment of the existing bungalow.
- The development is out of keeping with the street.
- The construction of the works will result in noise and disruption.
- Concerns surrounding the unloading of building materials.
- Neighbouring properties include a covenant preventing works from taking place.
- Concerns surrounding surface water drainage.

### **5.0 APPRAISAL**

**KEY ISSUES:**

- Impact on the openness of the Green Belt
- Visual impact on the dwelling and surrounding area
- Impact on neighbouring amenity

**RELEVANT PLANNING POLICY:**

5.1 Section 38(6) of the Planning and Compulsory Purchase Act 2004 requires that planning applications be determined in accordance with the development plan unless material considerations indicate otherwise. The development plan for York consists of the saved policies of the revoked Yorkshire and Humber Regional Spatial Strategy (RSS) relating to the general extent of the York Green Belt.

#### Saved Policies of the Yorkshire and Humber RSS

5.2 The Yorkshire and Humber RSS was revoked in 2013 with the exception of the policies relevant to the York Green Belt. Policy YH9(C) states that the detailed inner boundaries of the Green Belt around York should be defined in order to establish long term development limits that safeguard the special character and setting of the historic city.

5.3 Figure 6.2 of the RSS illustrates the general extent of the Green Belt outer boundary as being about 6 miles (10km) from York city centre. The application site is located approximately 6km from the city centre. It is on land proposed to be within the Green Belt in the 2018 Publication Draft Local Plan. The site is thus considered to fall within the general extent of the Green Belt.

#### National Planning Policy Framework

5.4 Paragraph 130 states that planning policies and decisions should ensure that developments will achieve a number of aims, including:

- function well and add to the overall quality of the area, not just for the short term but over the lifetime of the development
- be visually attractive as a result of good architecture, layout and appropriate and effective landscaping
- are sympathetic to local character and history, including the surrounding built environment and landscape setting
- create places that are safe, inclusive and accessible and promote health and well-being with a high standard of amenity for existing and future users.

5.5 The NPPF also places great importance on good design. Paragraph 134 says development that is not well designed should be refused especially where it fails to reflect local design policies and government guidance on design. Significant weight should be given to:

- a) development which reflects local design policies and government guidance on design, taking into account any local design guidance and supplementary planning documents such as design guides and codes; and/or

- b) outstanding or innovative designs which promote high levels of sustainability, or help raise the standard of design more generally in an area, so long as they fit in with the overall form and layout of their surroundings.

5.6 In respect of Green Belt paragraph 137 states the Government attaches great importance to Green Belts. The fundamental aim of Green Belt policy is to prevent urban sprawl by keeping land permanently open; the essential characteristics of Green Belts are their openness and their permanence. Paragraph 149 states that the construction of new buildings is inappropriate in the Green Belt other than in some listed exceptions. One of these exceptions is the extension or alteration of a building, provided that it does not result in disproportionate additions over and above the size of the original dwelling.

#### Publication Draft Local Plan 2018

5.7 The Publication Draft Local Plan ('2018 Draft Plan') was submitted for examination on 25 May 2018. In accordance with paragraph 48 of the NPPF, the Draft Plan policies can be afforded weight according to:

- The stage of preparation of the emerging plan (the more advanced the preparation, the greater the weight that may be given);
- The extent to which there are unresolved objections to relevant policies (the less significant the unresolved objections, the greater the weight that may be given); and
- The degree of consistency of the relevant policies in the emerging plan to the policies in the previous NPPF published in March 2012. (NB: Under transitional arrangements plans submitted for examination before 24 January 2019 will be assessed against the 2012 NPPF).

5.8 Policy D1 (Placemaking) seeks development proposals improve poor existing urban and natural environments, enhance York's special qualities, better reveal the historic environment and protect the amenity of neighbouring residents.

Development proposals that fail to make a positive contribution to the city or cause damage to the character and quality of an area or the amenity of neighbours will be refused.

5.9 Policy D11 (Extensions and Alterations to Existing Buildings) states that proposals to extend, alter or add to existing buildings will be supported where the design responds positively to its immediate architectural context, local character and history in terms of the use of materials, detailing, scale, proportion, landscape and space between buildings. Proposals should also sustain the significance of a heritage asset, positively contribute to the site's setting, protect the amenity of

current and neighbouring occupiers, contribute to the function of the area and protects and incorporates trees.

5.10 Policy GB1 (Development in the Green Belt) seeks to manage development in the Green Belt with the primary aim of preserving and enhancing the special character and setting of York and its villages.

#### Development Control Local Plan 2005

5.11 The York Development Control draft Local Plan was approved for development control purposes in April 2005. Its policies are material considerations in the determination of planning applications, although it is considered that their weight is limited except when they are in accordance with the NPPF.

5.12 Development Control Local Plan Policy CYH7 states that residential extensions will be permitted where (i) the design and materials are sympathetic to the main dwelling and the locality (ii) the design and scale are appropriate to the main building (iii) there is no adverse effect upon the amenities of neighbours.

5.13 Development Control Local Plan Policy GP1 refers to design for all types of development. Of particular relevance here are the criteria referring to good design and general neighbour amenity.

5.14 Development Control Local Plan Policy GB1 states planning permission for development in the Green Belt will only be granted where the scale, location and design of development would not detract from the openness of the Green Belt; it would not conflict with the purposes of including land within the Green Belt; and it would not prejudice or harm the elements which contribute to the special character and setting of York. It must also be for one of the specified purposes, which includes the limited extension, alteration and or replacement of existing buildings.

5.15 Development Control Local Plan Policy GB4 'Extensions to Existing Dwellings' states that the extension and alteration of dwellings in the Green Belt and open countryside will be permitted providing the proposal: would not cause undue visual intrusion; is appropriate in terms of design and materials and is small scale compared to the original dwelling. As a guide, a planning application to extend a dwelling by more than 25% of the original footprint will be considered to be large scale and resisted accordingly.

#### Supplementary Planning Document 'House Extensions and Alterations'

5.16 The Council has a draft Supplementary Planning Document 'House Extensions and Alterations' dated December 2012 which has been approved to provide interim planning guidance prior to adoption of the Local Plan on all types on domestic types of development. A basic principle of this guidance is that any extension should

normally be in keeping with the appearance, scale, design and character of both the existing dwelling and the road/streetscene it is located on. In particular, care should be taken to ensure that the proposal does not dominate the house or clash with its appearance with the extension/alteration being subservient and in keeping with, the original dwelling. Proposals should not unduly affect neighbouring amenity with particular regard to privacy, overshadowing and loss of light, over-dominance and loss of outlook. Guidance in sections v (character and streetscene) and xvi (Green Belt) are relevant to the determination of the application.

## ASSESSMENT

### IMPACT ON THE OPENNESS OF THE GREEN BELT

5.17 The extension or alteration of a building, provided it does not result in disproportionate additions over and above the size of the original, is not inappropriate development in the Green Belt.

5.18 The proposed works will not significantly impact the overall dwelling's footprint; the extension will replace the existing garage and rear lean-to. The works would not erode the openness of the Green Belt given their scale and similarity to the current dwelling and garage. The hip to gable roof extension will be visible from the front, but it doesn't result in an increase in height when compared to the existing ridge and its overall massing.

5.19 There is no conflict with Green Belt policy. The proposals have no material effect on the openness of the Green Belt and do not constitute inappropriate development in the Green Belt.

### VISUAL IMPACT ON DWELLING AND THE SURROUNDING AREA

5.20 This application seeks planning permission for a single storey side and rear extension and a loft conversion with hip to gable roof extension, dormer to rear and 2no. roof lights to the front.

5.21 The single storey rear extension will replace both the existing garage and rear extension. It will be "L" shaped, projecting 3.5m from the rear wall of the main dwelling before extending out at the side of the dwelling and replacing the existing detached garage's footprint. The extension will have a flat roof, a total height of 2.95m and the walls finished in render (off-white in colour).

5.22 Given the majority of the extension will be to the rear elevation along with the fact it will create a similar-sized footprint to the current dwelling's layout, it is not deemed to cause any significant harm to the host dwelling's appearance and would not appear as a visually prominent addition to the dwelling. Whilst the use of render does not match the host dwelling, it is not considered to cause any significant harm

to the overall appearance of the dwelling. The rendered areas do not materially affect the principle elevation of the host dwelling and there are a variety of cladding materials used locally.

5.23 The existing hipped roof would be altered to form a gable. A flat roof box dormer is also proposed that would span the rear roof plane of the original dwelling and hip to gable enlargement. The box dormer would be stepped down from the ridge and up from the eaves as well as being set in at both sides. The gable extension is proposed to use matching bricks and tiles to the existing house while the proposed dormer is to be finished in timber cladding. While the timber cladding will not match the existing roof tiles, it is not considered to be significantly harmful given the cedar cladding is deemed to somewhat represent the colour as the existing roof tiles. A condition is proposed to ensure the proposed timber cladding finish is approved before use to ensure it is appropriate in colour. The windows in the proposed dormer are considered to be appropriate in appearance and size when viewed in comparison to the existing windows.

5.24 Although the appearance of the dwelling will be altered by the proposed roof additions, but for the use of the timber cladding, rather than matching roof tiles, the roof extensions would fall under permitted development. The use of timber cladding is a contrast to the roof tiles and is not considered to cause harm to visual amenity.

5.25 The hip to gable roof extension will alter the appearance of the dwelling and its relationship with the attached and adjoining bungalows. However typically such changes to the roof shape of dwellings (undertaken in isolation) are permitted development, and subsequently are commonplace in suburban areas such as this. There are a variety of house types along Moor Lane, this includes bungalows with dormers added and hip to gable conversions. In this context, the roof extensions would not be unduly out of character. It would be unreasonable to refuse the application on design grounds.

5.26 The proposed roof lights do not require any formal consent, have a low visual impact, and therefore are deemed to be acceptable. The scheme has been altered to maintain the use of white UPVC windows at both the front and side to be in keeping with the neighbouring properties when viewed from the highway.

5.27 Overall, the development is not considered to significantly impact the appearance of the street. The use of materials that are not a precise match to the host building are at the rear, where their visual impact does not affect the streetscene.

There are also a variety of dwelling types and materials on show along Moor Lane. The proposal is not deemed to cause a level of harm to both the host dwelling itself or the street that it would warrant a refusal.

## NEIGHBOUR AMENITY

5.28 No.31 Moor Lane (attached) is not considered to be significantly affected by the proposed works. The single storey side and rear extension will be of such a size and distance from No.31 that it is not deemed to cause any outlook or dominance concerns. The extension has a similar footprint to the existing rear lean-to and garage. The closet part of the extension will be over 5m from the shared boundary and because of this, along with both its height and the sun's orientation, the extension will not lead to any overshadowing or loss of light to No.31. The extension is also not deemed to cause any privacy concerns. Although a side window is proposed it is not considered to lead to any overlooking; the existing boundary will partly screen it from view. The hip to gable extension is not deemed to lead to any harm to No.31 given it will be screened by the host dwelling. While the dormer does introduce three new windows to the rear, they do not look directly into any neighbouring windows and are therefore are not deemed to cause any direct overlooking concerns that would impact the day-to-day living of the neighbour. It is acknowledged the windows within the dormer will result in No.31's rear garden being overlooked but given the dormer houses two bedrooms and a bathroom, neither of these rooms are considered to be locations within a house one spends large amounts of time in and in reality the chances of any direct overlooking is minimal. Rear dormers can be added to dwellings under permitted development rights. It is typical in suburban locations upper floors and dormer windows allow a degree of overlooking into neighbours gardens. The proposed dormer raises no undue overlooking issues in this case. Due to the sun's orientation, the dormer would also not lead to any direct loss of light to No.31's rear openings.

5.29 No.27 Moor Lane is also not considered to be significantly affected by the proposed works. The extension is not deemed to cause any neighbouring harm to No.27's property given it will sit behind No.27's garage, outbuilding and car porch resulting in no harm with regards to outlook, dominance, privacy and loss of light. It is also not considered to lead to any outlook, dominance or privacy concerns. The dormer again will not lead to any direct overlooking into No.27's rear windows. The windows will lead to the possible overlooking of No.27's rear garden but given the separation distance between the properties and the location of both the host dwelling's new extension and No.27's garage, the overlooking impact is reduced. In addition to this, it is notable that No.23 Moor Lane is a two storey dwelling that already appears to overlook the gardens of the surrounding bungalows and due to this, it could be suggested the dormer windows do not create a new arrangement with first-floor windows already in situ in the immediate area. Due to the separation distance, the dormer is also not considered to lead to any loss of light to No.27's openings. The extensions proposed would not have a material impact on daylight and sunlight to the front or rear gardens of the neighbour, nor would there be affect to primary windows on the front and rear of the house.

5.30 All other surrounding neighbours are a sufficient distance away and would not be adversely affected by the proposal.



## OTHER MATTERS

5.31 The increase in noise between dwellings through the addition of the loft conversion is not a material consideration. This is a matter for Building Regulations.

5.32 In response to the concerns surrounding noise and disruption caused by the building works such as the unloading of building materials, this again wouldn't form part of the decision-making process and is therefore not a material consideration for a domestic project such as this.

5.33 A representation advises that the property may feature a covenant preventing works from taking place without consent from the original land owner/property developer. Any covenant in place would not be superseded by any planning consent and is not a material consideration. It would be a legal issue between the applicant and interested parties.

5.34 The works are for a householder extension. They do not significantly alter the overall footprint of development on site, as such and when taking into account what could be added to the property without planning consent, it would impractical and unreasonable impose any conditions in respect of drainage.

## 6.0 CONCLUSION

6.1 Taking into account relevant Green Belt policy and design guidance approval is recommended. The proposed extensions are not considered to result in a disproportionate addition to the existing dwelling, and would not impact on the openness of the Green Belt. The extension would have no undue effect on visual amenity and would not have a significant, or undue impact on neighbour amenity.

## 7.0 RECOMMENDATION: Householder Approval

1 TIME2 Development start within three years

2 The development hereby permitted shall be carried out in accordance with the following plans:-

Proposed Site Layout Plan - Drg. No: YB750 - 007 REV A (Dated 13.06.2020)

Proposed Ground Floor Plans - Drg. No: YB750 - 005 REV A (Dated 13.06.2020)

Proposed Attic Plan & Typical Section - Drg. No: YB750 - 006 REV A (Dated 13.06.2020)

Existing and Proposed Elevations - Drg. No: YB750 - 004 REV A (Dated

Application Reference Number: 22/00872/FUL

Item No: 4b

13.06.2020)

Reason: For the avoidance of doubt and to ensure that the development is carried out only as approved by the Local Planning Authority.

3 The materials used externally shall be as specified on approved drawings (condition 2), unless otherwise agreed in writing by the Local Planning Authority prior to their use. The roof tiles and brickwork of the proposed hip to gable roof extension shall match those of the existing house in colour, size, shape and texture.

Samples of the external cladding to the dormer and render to the extension shall be submitted to and approved in writing by the Local Planning Authority prior to construction of the relevant works and the development shall be carried out in accordance with the approved details.

Reason: In the interests of visual amenity and for the avoidance of doubt and to ensure the development is carried out only as approved by the Local Planning Authority.

## **8.0 INFORMATIVES: Notes to Applicant**

### **1. STATEMENT OF THE COUNCIL`S POSITIVE AND PROACTIVE APPROACH**

In considering the application, the Local Planning Authority has implemented the requirements set out within the National Planning Policy Framework (paragraph 38) in seeking solutions to problems identified during the processing of the application. The Local Planning Authority advised the agent the dormer was too large and matching windows would need to remain at the front of the property so as to be in keeping with the adjoining properties and not impact the streetscene. The agent reduced the dormer to be under 50 cubic metres and alter the front and side windows to white UPVC thus a positive outcome was achieved.

### **2. THE PARTY WALL ETC ACT 1996**

The proposed development may involve works that are covered by the Party Wall etc Act 1996. An explanatory booklet about the Act is available at:

<https://www.gov.uk/party-wall-etc-act-1996-guidance>

Furthermore the grant of planning permission does not override the need to comply with any other statutory provisions (for example the Building Regulations) neither does it override other private property rights (for example building on, under or over, or accessing land which is not within your ownership).

### 3. INFORMATIVE REGARDING ELECTRIC VEHICLE (EV) CHARGE POINTS

The Government's Electric Vehicle Homecharge Scheme' offers a grant to reduce the cost of installing a home electric vehicle charge point. For more information see the Office for Zero Emission Vehicles' (OZEV) website at:

<https://www.gov.uk/government/collections/government-grants-for-low-emission-vehicles>. All electrical circuits/installations should comply with the electrical requirements in force at the time of installation.

### 4. SURFACE WATER DRAINAGE

The owner should, where practical, seek to use sustainable drainage methods at the property, in order to reduce the rate of surface water run-off into the local watercourses. Examples include the installation of water butts (rainwater harvesting), use of green roofs, removal of existing areas of hard standing or the use of porous materials for new areas of hard surfacing.

**Contact details:**


**Case Officer:** Ed Bainbridge

**Tel No:** 01904 554033

This page is intentionally left blank

# 29 Moor Lane, Acomb, York YO24 2QX

22/00872/FUL



Scale : 1:1616

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationery Office © Crown Copyright 2000.

Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings.

<b>Organisation</b>	City of York Council
<b>Department</b>	Directorate of Place
<b>Comments</b>	Site Location Plan
<b>Date</b>	21 July 2022
<b>SLA Number</b>	

This page is intentionally left blank



# Planning Committee B

To be held on Thursday 11<sup>th</sup> August 2022 at 4:30pm


# 22/00872/FUL - 29 Moor Lane Acomb York YO24 2QX

Single storey side and rear extensions after demolition of existing garage, and loft conversion with hip to gable roof, dormer to rear and 2no. rooflights to front (part retrospective)










Ground floor plan



Proposed Attic Plan & Typical Section - 29 Moor Lane, York, YO24 2QX

Roof floor plan

Elevations

**Existing Front Elevation**

**Existing Side Elevation**

**Existing Rear Elevation**

**Existing Side Elevation**

**Proposed Front Elevation**

**Proposed Side Elevation**

**Proposed Rear Elevation**

**Proposed Side Elevation**

NOTE: EXISTING FRONT AND SIDE WINDOWS TO BE WHITE UPVC

A	A2	NEW WINDOWS INDICATED IN RED NEW EXISTING INDICATED IN BLUE NEW AND EXISTING TO BE WHITE UPVC	13.06.22
REV	BY	DATE	
<b>COMPLETE PLANS LTD</b> ARCHITECTURAL DESIGN			
4 LAURE LANE, YORK, YO24 2QU T: 01904 881770 M: 07782 276558 E: andy.walton@cp.com			
PROJECT: 29 Moor Lane, York, YO24 2QX TITLE: Existing & Proposed Elevations CLIENT: Mr R Grant DATE: April 2022 SCALE: 1:100 @ A2 DRAWING NO: YB150 - 004 REVISION: A DRAWN: AS CHECKED:			
APPROVED FOR THE ARCHITECT BY: [Signature] APPROVED FOR THE CONTRACTOR BY: [Signature]			

Existing & Proposed Elevations - 29 Moor Lane, York, YO24 2QX