SCHOOL CROSSING PATROL (SCP) CRITERIA COUNT

School	Park Grove Primary	Survey	Lowther Street
		Location	adjacent to rear
			school entrance
Surveyor	Jayne Ward	Date	Tuesday
			24/02/2015
Time Period	0830 to 0900hrs	Weather	Overcast

Total child pedestrians (P) crossing within 50m of the survey location during the	40
peak half hour	

Vehicle Type	PCU [*] Value	Count	Equivalent PCUs
Private Car / Light Goods Vehicle (<3.5T)	1	198	198
Motorcycle	1/2	2	1
Cycle	1/3	6	2
MGV**(3.5 - 7.5T)	2	3	6
HGV***(>7.5T)	3	2	6
Total PCUs (V)	213		


The crossing assessment is based on the PV² value

Lowther Street $PV^2 = 40 \times (213)^2 = 1814760$

This figure falls far short of the 4 million PV² value that the national guidelines recommend that a SCP site be established.

Looking at Chart 1 over the page, which is extracted from the SCP Guidelines, this count falls in to area C which means that a SCP is definitely not justified at initial assessment and that Part 4 of the assessment guidelines should only be used to verify the position in exceptional circumstances. Part 4 of the SCP guidelines deals with adjustment factors and takes into account factors affecting the crossing environment, traffic speed, pedestrian accident figures and the age of the children crossing.

Chart 1: Taken from the SCP Guidelines (Sept 2016)



For completeness the site has been put through the Part 4 process and applying the relevant adjustment factors this site adds a total of seven factors, made up of the following:

- Obstruction of sightlines of approaching drivers by parking bay and street furniture (+1)
- Site on a minor road within 20m of a junction (+1)
- Age factor children up to 11 years of age (+5)

The guidelines indicate that a total of seven factors would give a multiplier of 1.949.

Adjusted PV^2 = Original PV^2 x Multiplier = 1814760 x 1.949 Adjusted PV^2 = 3536967

This value is still below the threshold of 4 million therefore the site is not justified as a SCP site.

The count was carried out at the request of a local councillor wanting a crossing facility, either a zebra or push button. Because the count is so low the site fails to meet the criteria.

Having carried out the count it was observed that whilst the traffic flow can at times be heavy it is on a one-way street, often the traffic is stationary and pedestrians were observed to be able to cross fairly easily, there is also a build-out in the footpath at the entrance to school to assist crossing.