



## Notice of meeting of

### East Area Planning Sub-Committee

**To:** Councillors Moore (Chair), Cregan (Vice-Chair), Douglas, Firth, Funnell, Hyman, King, Orrell, Taylor and Wiseman

**Date:** Thursday, 21 August 2008

**Time:** 2.00 pm

**Venue:** The Guildhall, York

### AGENDA

Site Visits for this meeting will commence at 10.00am on Wednesday 20 August 2008 at Union Terrace Car Park

**1. Declarations of Interest**

At this point Members are asked to declare any personal or prejudicial interests they may have in the business on this agenda.

**2. Public Participation**

At this point in the meeting members of the public who have registered their wish to speak regarding an item on the agenda or an issue within the Sub-Committee's remit can do so. Anyone who wishes to register or requires further information is requested to contact the Democracy Officer on the contact details listed at the foot of this agenda. The deadline for registering is Wednesday 20 August at 5pm.

**3. Plans List**

To determine the following planning applications related to the East Area.

- a) **7 Fairfields Drive, Skelton, York, YO30 1YP.** (Pages 5 - 9)  
**(08/01640/FUL)**

Two storey extension to side, single storey extension to rear, pitched roof canopy to front, after demolition of existing garage. [Skelton, Rawcliffe and Clifton Without Ward] **[Site Visit]**

- b) **Archbishop Holgates School, Hull Road,** (Pages 10 - 22)  
**York, YO10 5ZA. (08/01266/FULM)**

Erection of 1 no two storey learning centre with associated access, landscaping, parking and cycle storage, following demolition of existing cycle storage (resubmission). [Hull Road Ward] **[Site Visit]**

#### **4. Urgent Business**

Any other business which the Chair considers urgent under the Local Government Act 1972

#### Democracy Officer:

Name: Laura Bootland

- Telephone – (01904) 552062
- E-mail – [laura.bootland@york.gov.uk](mailto:laura.bootland@york.gov.uk)

For more information about any of the following please contact the Democracy Officer responsible for servicing this meeting

- Registering to speak
- Business of the meeting
- Any special arrangements
- Copies of reports

Contact details set out above.

**EAST AREA PLANNING  
SUB-COMMITTEE****SITE VISITS****WEDNESDAY 20 August 2008**

<b>TIME</b>	<b>SITE</b>
<b>10:00 am</b>	<b>Meet Minibus at Union Terrace Car Park.</b>
<b>10:10 am</b>	<b>7 Fairfields Drive, Skelton (3a)</b>
<b>10:45am</b>	<b>Archbishop Holgates School (3b)</b>



## About City of York Council Meetings

### Would you like to speak at this meeting?

If you would, you will need to:

- register by contacting the Democracy Officer (whose name and contact details can be found on the agenda for the meeting) **no later than 5.00 pm** on the last working day before the meeting;
- ensure that what you want to say speak relates to an item of business on the agenda or an issue which the committee has power to consider (speak to the Democracy Officer for advice on this);
- find out about the rules for public speaking from the Democracy Officer.

**A leaflet on public participation is available on the Council's website or from Democratic Services by telephoning York (01904) 551088**

### Further information about what's being discussed at this meeting

All the reports which Members will be considering are available for viewing online on the Council's website. Alternatively, copies of individual reports or the full agenda are available from Democratic Services. Contact the Democracy Officer whose name and contact details are given on the agenda for the meeting. **Please note a small charge may be made for full copies of the agenda requested to cover administration costs.**

### Access Arrangements

We will make every effort to make the meeting accessible to you. The meeting will usually be held in a wheelchair accessible venue with an induction hearing loop. We can provide the agenda or reports in large print, electronically (computer disk or by email), in Braille or on audio tape. Some formats will take longer than others so please give as much notice as possible (at least 48 hours for Braille or audio tape).

If you have any further access requirements such as parking close-by or a sign language interpreter then please let us know. Contact the Democracy Officer whose name and contact details are given on the order of business for the meeting.

Every effort will also be made to make information available in another language, either by providing translated information or an interpreter providing sufficient advance notice is given. Telephone York (01904) 551550 for this service.

যদি যথেষ্ট আগে থেকে জানানো হয় তাহলে অন্য কোন অর্ধাতে তথ্য জানানোর জন্য সব ধরনের চেষ্টা করা হবে, এর জন্য দরকার হলে তথ্য অনুবাদ করে দেয়া হবে অথবা একজন দোঅবী সরবরাহ করা হবে। টেলিফোন নম্বর (01904) 551 550।

*Yeteri kadar önceden haber verilmesi koşuluyla, bilgilerin terümesini hazırlatmak ya da bir tercüman bulmak için mümkün olan herşey yapılacaktır. Tel: (01904) 551 550*

我們竭力使提供的資訊備有不同語言版本，在有充足時間提前通知的情況下會安排筆譯或口譯服務。電話 (01904) 551 550。

اگر مناسب وقت سے اطلاع دی جاتی ہے تو ہم معلومات کا ترجمہ مہیا کرنے کی پوری کوشش کریں گے۔ ٹیلی فون (01904) 551 550

*Informacja może być dostępna w tłumaczeniu, jeśli dostaniemy zapotrzebowanie z wystarczającym wyprzedzeniem. Tel: (01904) 551 550*

## **Holding the Executive to Account**

The majority of councillors are not appointed to the Executive (38 out of 47). Any 3 non-Executive councillors can 'call-in' an item of business from a published Executive (or Executive Member Advisory Panel (EMAP)) agenda. The Executive will still discuss the 'called in' business on the published date and will set out its views for consideration by a specially convened Scrutiny Management Committee (SMC). That SMC meeting will then make its recommendations to the next scheduled Executive meeting in the following week, where a final decision on the 'called-in' business will be made.

## **Scrutiny Committees**

The purpose of all scrutiny and ad-hoc scrutiny committees appointed by the Council is to:

- Monitor the performance and effectiveness of services;
- Review existing policies and assist in the development of new ones, as necessary; and
- Monitor best value continuous service improvement plans

## **Who Gets Agenda and Reports for our Meetings?**

- Councillors get copies of all agenda and reports for the committees to which they are appointed by the Council;
- Relevant Council Officers get copies of relevant agenda and reports for the committees which they report to;
- Public libraries get copies of **all** public agenda/reports.



2.2 Policies:

CYGP1  
Design

CYH7  
Residential extensions

**3.0 CONSULTATIONS**

EXTERNAL

3.1 Skelton Parish Council - Object on the following grounds:

- the extensions by virtue of their design, size and scale would dominate the site and would result in an overbearing and oppressive development when viewed from 9 Fairfields Drive;
- an appeal regarding the erection of a new dwelling within the rear garden has yet to be determined, fully considering the implications of this application without knowing whether a dwelling is to be built in the back garden is difficult;
- it appears unlikely that the development could be achieved without impacting upon the trees on the site.

3.2 Neighbours - No correspondence received.

**4.0 APPRAISAL**

4.1 The key issues to consider in determining this application are considered to be the visual impact on the street scene and the living conditions of neighbours.

STREET SCENE

4.2 The front of the property is the most visually important elevation within the street scene, the rear of the property is also visible from Grange Close, albeit above a 1.5 - 2 m close boarded boundary fence. The proposed two-storey side extension is considered to conform with the dwelling extension design guide. The extension is set back approximately 0.6 m from the main front elevation of the house. The ridge and eaves heights have also been reduced in relation to the main house. The extension would be 3.5 m in width whilst the main house is currently 8 m in width. Therefore the proposed extension is considered to be subservient to the main house. The proportions and detailing of the proposed extension appear considered in terms of the location and scale of the window and garage door openings.

4.3 The proposed canopy to the ground floor front elevation is not a common feature in the area. However, it is small in scale and subject to a condition ensuring that the building materials match those on the main house it is not considered that it would harm the appearance of the dwelling or the character of the area. There are a variety of house styles in the area and it is considered that the proposed addition would not be significantly detrimental to the street scene.



4.4 At present the rear of the property contains a full width conservatory. Part of the proposed development is to reduce the size of the conservatory and to replace this with an extension to the kitchen. It is considered that this would have very little impact on the appearance of the dwelling.

4.5 The two-storey side extension protrudes 2.4 m from the main rear elevation of the house. However, the proposed eaves height is set significantly below that of the main house creating an appearance similar to that of a dormer bungalow. This is an unusual design detail on this dwelling. Whilst this would be visible from some areas of Grange Close it is not considered that it would be visually prominent given the separation distance between the proposed extension and Grange Close. It is considered that the impact on the street scene would be limited and not significantly harmful.

#### LIVING CONDITIONS OF NEIGHBOURS

4.6 The proposed two-storey side extension would be located very close to the property curtilage boundary with 9 Fairfields Drive. 9 Fairfields Drive has an attached flat roof garage on the boundary which would separate the proposed extension from the main house. 9 Fairfields Drive only has one window in its side elevation facing the proposed development, this is at first storey level and is secondary in nature. The primary purpose of this window would be to provide natural light rather than an outlook. There are no windows within the side elevation of the proposed extension. Therefore the impact on the first floor window of number 9 is considered to be acceptable.

4.7 The proposed two-storey side extension protrudes beyond the main rear elevation of 7 Fairfields Drive. However, 9 Fairfields Drive is set back a greater distance from the road than number 7. The proposed two-storey rear extension would therefore not extend beyond the main rear elevation of 9 Fairfields Drive. Therefore, it is not considered that the extension would appear dominant or overbearing when viewed from this property. It is also not considered that there would be significant implications in terms of the blocking out of sunlight, the submitted sunlight assessment also concludes that this is the case.

4.8 The nearest dwelling to the rear is a bungalow at 2 Grange Close. This is over 20 m away from the proposed extension and therefore the impact on the living conditions of this property would be minimal.

4.9 The proposed extension would create a five-bedroom dwelling. Associated with the extension is an integral garage which can be used for car and cycle parking. There is also the capacity to park vehicles off the road at the front of the house. There are no highway objections to this application.

4.10 Skelton Parish Council raised concerns about the loss of trees on this site. No trees on the application site are protected and they could therefore be removed at any point without permission from the LPA. It is not considered that any trees or shrubs which may need to be removed to make way for the extensions significantly contribute to the character and appearance of the area.

## 5.0 CONCLUSION

5.1 It is considered that the proposed development would not harm the character and appearance of the street scene or the living conditions of neighbours. The application is therefore recommended for approval subject to conditions.

## COMMITTEE TO VISIT

**6.0 RECOMMENDATION:** Approve

1. TIME2 Development start within three years
2. The development hereby permitted shall be carried out only in accordance with the following plans:-

Drawing Number 08:49:01 Rev A received by The CoYC on 20/06/08.

Or any plans or details subsequently agreed in writing by the Local Planning Authority as amendment to the approved plans.

Reason: For the avoidance of doubt and to ensure that the development is carried out only as approved by the Local Planning Authority.

3. VISQ1 matching materials

## 7.0 INFORMATIVES: Notes to Applicant

### 1. REASON FOR APPROVAL


In the opinion of the Local Planning Authority the proposal, subject to the conditions listed above, would not cause undue harm to interests of acknowledged importance, with particular reference to the impact on the street scene and the living conditions of neighbours. As such the proposal complies with Policies GP1 and H7 of the City of York Draft Local Plan.

### Contact details:

**Author:** Michael Jones Development Control Officer  
**Tel No:** 01904 551325

# 7 Fairfields Drive

08/01640/FUL



Scale : 1:1250

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationery Office © Crown Copyright 2000.

Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings.

Produced using ESRI (UK)'s MapExplorer 2.0 - <http://www.esriuk.com>

<b>Organisation</b>	Not Set
<b>Department</b>	Not Set
<b>Comments</b>	Application Site
<b>Date</b>	11 August 2008
<b>SLA Number</b>	Not Set

**COMMITTEE REPORT**

**Committee:** East Area  
**Date:** 21 August 2008  
**Ward:** Hull Road  
**Parish:** Hull Road Planning Panel

**Reference:** 08/01266/FULM  
**Application at:** Archbishop Holgates School Hull Road York YO10 5ZA  
**For:** Erection of 1 no two storey learning centre with associated access, landscaping, parking and cycle storage following demolition of existing cycle storage (resubmission)  
**By:** Archbishop Holgates School  
**Application Type:** Major Full Application (13 weeks)  
**Target Date:** 29 August 2008

**1.0 PROPOSAL**

1.1 This is a full planning application for the erection of an extension to Archbishop Holgate's school to provide accommodation for post 16 education.

1.2 In December 2006 Archbishop Holgate's school was advised that it had been redesignated as a high performing specialist science college with a second vocational specialist status thus creating an opportunity to apply for the provision of post 16 education.

1.3 A feasibility study undertaken at Archbishop Holgate's school concluded that through the development of a new purpose built applied learning centre Archbishop Holgate's school could promote partnership working to the delivery of the 16 - 19 agenda in a way that meets the needs of learners and offers focused educational provision addressing demand from some of the key economic drivers within the city.

1.4 Archbishop Holgate's school is located on Hull Road approximately 1.5 miles to the east of York city centre. It is a voluntary aided mixed gender secondary school with science college status, and designated as a high performing school with applied learning status. It currently serves approximately 850 students in the 11 - 16 age group, mainly within the south and east areas of York.

1.5 The 8.5Ha site is located directly adjacent to Hull Road to the south. The surrounding development is primarily low rise residential, the Black Bull Hotel, and low rise motel, on the western perimeter.

1.6 The school site is a single, two and three storey mixed development, based on an original school development in 1963. This was significantly enlarged in the 1970's with successive further developments to date. The main buildings are located towards the northern part of the site. The southern part of the site comprises the school grounds, mainly playing fields. The main entrance and exit point for both vehicular and pedestrian traffic is located on Yarburgh Way on the north eastern side of the site.

1.7 The proposal is to construct a two storey building to accommodate approximately 1730 square metres of floor space. The overall size of the building is 46 metres by 19 metres with a maximum height of 9.75 metres. The building is to be sited directly adjacent to the east wing of the building on an existing hard standing which is currently used as the car park and will provide accommodation for 160 pupils and 10 staff. The proposal includes 30 parking spaces( including 2 disabled spaces) , 58 cycle parking spaces and motorcycle parking adjacent to the new applied learning centre. The main car parking that is currently located on the site of the new building is to be relocated to the front of the school building. This area provides 85 car parking spaces ( Including 5 disabled spaces) and 300 covered cycle parking spaces. It is also proposed to widen a portion of the internal access road to 5.5 metres to provide a passing place for vehicles entering and leaving the site. Vehicular entrance enhancements proposed on the original scheme have been deleted from this application.

1.8 The application is supported by a design and access statement which incorporates sustainability measures.

## **2.0 POLICY CONTEXT**

2.1 Development Plan Allocation:

City Boundary York City Boundary 0001

DC Area Teams East Area (1) 0003

Schools Badger Hill Primary 0184

Schools Archbishop Holgate's CE 0243

2.2 Policies:

## **3.0 CONSULTATIONS**

Internal

Highways Network Management

3.1 The previous application included proposed works to the entrance that were not favoured by highways as they were considered to disadvantage pedestrian movements at and around the main entrance. If amendments to the entrance are still envisaged then details must be submitted for consideration.

3.2 It is also noted that motorcycle and extensive cycle parking/storage areas are to be provided but no details are shown. It is considered that this could be covered by condition.

3.3 It is also noted that a large area of car parking is to be formed with "Grasscrete". This area would be over 200m from the public highway and consequently it is not considered that there would be any significant "carry over" of loose material onto the public highway. Its construction and use is therefore not objected to subject to standard conditions being applied.

3.4 Notwithstanding the above comments Highways Network Management do not object to the application subject to conditions that ensure the appropriate execution of the scheme, the submission of a travel plan and a condition requiring the submission of details of the covered cycle and motor bike parking.

#### Environmental Protection

3.5 The Environmental Protection Unit have no objections to the application however it is recommended that a condition is attached to ensure any plant / machinery installed as a result of this application does not affect the amenity of local residents through noise. A demolition and construction informative is also suggested.

#### Structures and Drainage

3.6 No objections to the proposal provided the maximum discharge rate does not exceed 5 litres per second.

#### Landscape Architect

3.7 The Landscape Architect does not object to the principle of the development however there are two trees that will be lost by the positioning of the car park which it is considered should be retained. It is requested that the cycle parking is amended to allow the trees to be kept. A landscaping condition and tree protection condition are also proposed.

#### External

##### Hull Road Planning Panel

3.8 Hull Road Planning panel support this application

##### Sport England

3.9 Sport England objected to the last application for the extension of the school because the proposed location of the car parking would result in the loss of a playing pitch and athletics provision. The resubmission now proposes to place the car parking adjacent to the existing rugby pitch on an area of land that is currently sloping and would not be capable of forming a pitch. Therefore, as the development will not impact on any of the existing pitches or safety margins, sport England is satisfied that the development is acceptable when assessed against their policies.

#### Publicity

3.10 The application was advertised by means of a site notice posted on the 10th June 2008 and via a press advert dated the 11th June 2008. Properties surrounding the site were also consulted on the application on the 3rd June 2008.

## 4.0 APPRAISAL

### 4.1 Key Issues

- Policy background
- Design and landscape considerations
- Traffic, highways and access issues
- Playing field provision
- Drainage
- Sustainability
- Impact on Residential amenity

### Policy Background

4.2 The application relates to the erection of an extension to an existing school to provide facilities for 16 to 18 year olds. The site is identified as an educational establishment in the Draft Local Plan.

4.3 The regional spatial strategy adopted May 2008 says little about education, however policy E1 makes reference to the need to support higher and further education to ensure a knowledge driven economy. Paragraph 11.3 says that there needs to be an ongoing focus on education skills, training and training entrepreneurs.

4.4 The draft local plan sets out educational objectives, one of which is to foster a culture of education, life-long learning and to widen access to education. Policy ED1 in relation to Primary and secondary education says that new secondary education facilities will be granted provided that it would meet a recognised need, the development is of a scale and design appropriate to the character and appearance of the locality and an area of open space and playing fields, sufficient to meet the needs of pupils is incorporated in the development and where a development is capable of a joint or dual use for community benefit, this has been incorporated into the design. Policy ED11 says the loss of playing fields associated with educational establishments will not be permitted unless exceptional circumstances are proven to exist.

4.5 Other relevant local plan policies include GP1 (Design), which states that development proposals will be expected (inter alia) to respect or enhance the local environment, be of a density, layout, scale, mass and design that is compatible with neighbouring buildings, spaces and the character of the area, using appropriate building materials, and avoiding the loss of open spaces, important gaps within development, vegetation, water features and other features that contribute to the quality of the local environment. Policy GP4a requires new development to have regard to the principles of sustainable development as set out in the policy and expanded upon within the Interim Planning Statement on sustainable design and construction.

4.6 Policy GP7 says that the development of land designated as open space will only be permitted where there will be no detrimental effect on local amenity or nature conservation and compensatory provision of an equivalent size and standard is provided. Policy GP9 states that where appropriate, development proposals will be required to incorporate a suitable landscaping scheme, which must be planned as an

integral part of the proposals, include an appropriate range of indigenous species, reflect the character of the locality and surrounding development and form a long term edge to developments adjoining or in open countryside.

#### Design and Landscape Considerations

4.7 It is proposed to site the building on the existing car park located adjacent to the east wing of the existing building. The land beyond the car park area drops away to the playing fields. The playing fields separating the site from surrounding residential properties. The design of the building is similar in scale to the rest of the school and has been designed to be consistent with the external form of existing buildings. As the extension will be sited immediately adjacent to the existing school buildings, with consistent visual form and scale, it is anticipated that its presence will not affect the visual amenity of the area.

4.8 In terms of landscape the proposal intends keeping all the existing landscaping around the area of the site where the extension is to be built. This area would also benefit from additional planting, particularly to soften the development when viewed from the residential properties to the rear. The submission of a landscaping scheme will be conditioned. In relation to the proposed car park; there are four trees that will be affected by the new car park and cycle parking position. The Landscape Architect is concerned about the loss of two of the trees a lime and a maple which are good specimens and has asked for the layout to be amended to ensure that these trees can be retained. An amended plan is expected to deal with the Landscape Architects concern, the details of the amendment will be reported direct to committee. In all other respects the position of the new parking arrangements is considered to be acceptable; it is well related to the buildings reception area and provides the site with a better overall layout. Additional landscaping through a landscaping scheme will help assimilate the car park in to the site and provide 'softening' to the gabion wall needed to retain soil where levels change between the playing field and car parking area.

#### Traffic, highways and access issues

4.9 The proposal includes 30 parking spaces (including 2 disabled spaces) , 58 cycle parking spaces and motorcycle parking adjacent to the new applied learning centre. The main car parking that is currently located on the site of the new building is to be relocated to the front of the school building. This area provides 85 car parking spaces (Including 5 disabled spaces) and 300 covered cycle parking spaces. It is also proposed to widen a portion of the internal access road to 5.5 metres to provide a passing place for vehicles entering and leaving the site. Vehicular entrance enhancements proposed on the original scheme have been deleted from this application.

4.10 Highways Network Management raise no objections to the proposals subject to conditions which ensure the proper implementation of the scheme and the submission of a travel plan. The parking provision is well related to the entrances to the building and is considered to provide an overall better arrangement that exists at the site.



### Playing Field Provision

4.11 Sport England have considered this application in the context of their policy which opposes any grant of planning permission for any development which would lead to the loss of or prejudice the use of any part of a playing field. The previous application for the proposal was objected to because the car park was sited so that a significant amount of playing field would be lost. Sport England have concluded that the proposed development affects only land incapable of forming, or forming part of, a playing pitch and does not result in the loss of or inability to make use of any playing pitch, a reduction in size of the playing area of any playing pitch or the loss of any sporting/ ancillary facilities on site and are therefore not objecting to the application.

### Drainage

4.12 The site is located within flood zone 1. Structures and Drainage have confirmed that details submitted to deal with surface water run off are acceptable. A condition is proposed to ensure that the maximum discharge rate proposed is achieved and maintained on site. The Environment Agency has been consulted on the application because the application site exceeds 1 Ha. Any comments received will be reported direct to committee.

### Sustainability

4.13 The design and access statement sets out the sustainability measures that will be undertaken to achieve a BREEAM assessment very good. Measures include a Building Energy Management System which provides time and temperature control functions for heating, domestic hot water and mechanical ventilation systems, rainwater harvesting and ground source heating. A condition is proposed to ensure a BREEAM very good is achieved. The measures proposed within the development are considered to be in accordance with GP4a and the interim planning statement relating to sustainable development.

### Impact on Residential Amenity

4.14 The siting of the proposed extension is set well away from residential properties and whilst these properties will be aware of the change in the appearance of the school as a result of the building there will be no detrimental impact on the residential amenity of properties as a result of the extension.

4.15 The new car parking area on the west of the site will increase vehicle, cycle and pedestrian movements adjacent to the sites boundary with the public house . However the boundary between the sites is well established and positioning of the cycle and car parking in its proposed location will not in Officer view detract from the operation of the public house. Properties on Sails drive to the rear of the public house will not be affected by the development.

## 5.0 CONCLUSION

5.1 Archbishop Holgate's School has been identified as a high performing school and a feasibility study for the school has concluded that through the erection of a new purpose built applied learning centre the school could promote partnership working to deliver 16-19 year old education. In terms of its design and siting and highways, traffic and access issues the proposal is considered to be acceptable and in accordance within policy ED1 and GP1 of the Draft Local Plan.

5.2 The proposal will not result in the loss of playing field facilities and therefore accords with the requirements of ED11 and will provide sustainability measures in accordance with policy GP4a and the Interim Planning Statement on Sustainable development.

5.3 Whilst the development will be visible to surrounding properties, it is sited sufficient distance from the boundaries of the site not to cause disturbance or be in any way visually dominant and therefore complies with the requirements of GP1 in so far as it relates to residential amenity.

## 6.0 RECOMMENDATION: Approve

- 1 TIME2 Development start within three years
- 2 The development hereby permitted shall be carried out only in accordance with the following plans and other submitted details:-

071368 103E  
071368 104E  
071368 106E  
071368 135A  
28298/207  
28298/202A  
28298/200A  
28298/103  
28298/100A  
28298/101  
28298/102  
28298/01  
28298/02  
28298/03  
28298/04  
28298/05  
28298/06  
28298/07

Design and Access statement incorporating sustainability details received 27th May 2008

or any plans or details subsequently agreed in writing by the Local Planning Authority as an amendment to the approved plans.

Reason: For the avoidance of doubt and to ensure that the development is carried out only as approved by the Local Planning Authority.

3 No development shall take place until there has been submitted and approved in writing by the Local Planning Authority a detailed landscaping scheme which shall illustrate the number, species, height and position of trees and shrubs . This scheme shall be implemented within a period of six months of the completion of the development. Any trees or plants which within a period of five years from the completion of the development die, are removed or become seriously damaged or diseased shall be replaced in the next planting season with others of a similar size and species, unless alternatives are agreed in writing by the Local Planning Authority.

Reason: So that the Local Planning Authority may be satisfied with the variety, suitability and disposition of species within the site.

4 Before the commencement of development including excavations, site clearance, building operations, or the importing of materials, a method statement regarding protection measures for the existing trees to be retained shall be submitted to and approved in writing by the Local Planning Authority. This statement shall include details and locations of protective fencing to be shown on a plan; site access during demolition/construction; arrangements for loading/off-loading; parking arrangements for site vehicles; locations for storage of materials; location of site compound.

The protective fencing line shall be adhered to at all times during development to create exclusion zones. None of the following activities shall take place within the exclusion zones: excavation, raising of levels, storage of any materials or top soil, lighting of fires, parking or manoeuvring of vehicles. Within the exclusion zones there shall be no site huts, no mixing of cement, no disposing of washings, no stored fuel, no new service runs or drains et al.

Reason: To ensure protection of existing trees before, during and after development which are covered by a Tree Preservation Order and/or make a significant contribution to the amenity of the area and/or development.

5 HWAY10 Vehicular areas surfaced, details reqd

6 HWAY18 Cycle parking details to be agreed

7 HWAY19 Car and cycle parking laid out

8 The development hereby permitted shall not come into use until secure and covered motorcycle parking facilities have been provided in accordance with details that have been submitted to and approved in writing by the LPA. Thereafter the parking facilities shall be retained free of all obstructions that would prevent their

intended purpose.

Reason - To promote alternative means of commuting to the private car thereby reducing congestion on the adjacent roads

9 Prior to the commencement of the development hereby permitted an amended School Travel Plan for Archbishop Holgates School incorporating the proposed learning centre or solely for the proposed learning centre, as deemed appropriate, shall be submitted to and agreed in writing by the LPA and thereafter such measures as may be contained therein shall be adhered to.

Reason: To ensure the development complies with advice contained in PPG 13-Transport, and in Policy T20 of the City of York deposit Draft Local Plan, and to ensure that adequate provision is made for the movement of vehicles, pedestrians, cycles and other modes of transport to and from the site, together with provision of parking on site for these users

10 Details of all machinery, plant and equipment to be installed in or located on the use hereby permitted, which is audible outside of the site boundary when in use, shall be submitted to the local planning authority for approval. These details shall include maximum sound levels ( $L_{Amax}(f)$ ) and average sound levels ( $L_{Aeq}$ ), octave band noise levels and any proposed noise mitigation measures. All such approved machinery, plant and equipment shall not be used on the site except in accordance with the prior written approval of the local planning authority. The machinery, plant or equipment and any approved noise mitigation measures shall be fully implemented and operational before the proposed use first opens and shall be appropriately maintained thereafter.

Reason: To protect the amenity of local residents.

11 The developer shall aim to achieve a BREEAM "very good" or "excellent" assessment standard for the development. Unless otherwise agreed in writing by the Council within 1 month of the date of the commencement of construction of the development the developer shall submit in writing for the approval of the Local Planning Authority a BREEAM design assessment demonstrating the progress of the BREEAM assessment, the percentage score expected to be achieved and which standard this relates to. Where this does not meet at least a 'very good' standard then the developer must demonstrate what changes will be made to the development to achieve at least 'very good' standard.

Reason. To ensure that the development is sustainable and accords with Policy GP4A of the draft City of York Local Plan.

12 VISQ8 Samples of exterior materials to be app

13 The maximum rate of discharge from the proposed development must be no greater than 5 l/s.

Reason: To prevent the increased risk of flooding.

**7.0 INFORMATIVES:  
Notes to Applicant**

1. REASON FOR APPROVAL

In the opinion of the Local Planning Authority the proposal, subject to the conditions listed above, would not cause undue harm to interests of acknowledged importance, with particular reference to:-

- Design and landscape considerations
- Traffic, highways and access issues
- Playing field provision
- Drainage
- Sustainability
- Impact on Residential Amenity

As such the proposal complies with Policies ED1, ED11, GP1, GP4a, and GP9 of the City of York Local Plan Deposit Draft.

2. Contaminated Land

If, as part of the proposed development, the applicant encounters any suspect contaminated materials in the ground, the Contaminated Land Officer at the council's Environmental Protection Unit should be contacted immediately. In such cases, the applicant will be required to design and implement a remediation scheme to the satisfaction of the Local Planning Authority. Should City of York Council become aware at a later date of suspect contaminated materials which have not been reported as described above, the council may consider taking action under Part IIA of the Environmental Protection Act 1990.

3. CONTAMINATION

If, as part of the proposed development, the applicant encounters any suspect contaminated materials in the ground, the Contaminated Land Officer at the council's Environmental Protection Unit should be contacted immediately. In such cases, the applicant will be required to design and implement a remediation scheme to the satisfaction of the Local Planning Authority. Should City of York Council become aware at a later date of suspect contaminated materials which have not been reported as described above, the council may consider taking action under Part IIA of the Environmental Protection Act 1990.

4. Construction Informative

The developer's attention should also be drawn to the various requirements for the control of noise on construction sites laid down in the Control of Pollution Act 1974. In order to ensure that residents are not adversely affected by air pollution and noise, the following guidance should be attached to any planning approval, failure to do so could result in formal action being taken under the Control of Pollution Act 1974:

1. All demolition and construction works and ancillary operations, including deliveries to and despatch from the site shall be confined to the following hours:

Monday to Friday	08.00 to 18.00
Saturday	09.00 to 13.00

Not at all on Sundays and Bank Holidays.

2. The work shall be carried out in such a manner so as to comply with the general recommendations of British Standards BS 5228: Part 1: 1997, a code of practice for "Noise and Vibration Control on Construction and Open Sites" and in particular Section 10 of Part 1 of the code entitled "Control of noise and vibration".

3. All plant and machinery to be operated, sited and maintained in order to minimise disturbance. All items of machinery powered by internal combustion engines must be properly silenced and/or fitted with effective and well-maintained mufflers in accordance with manufacturers instructions.

4. The best practicable means, as defined by Section 72 of the Control of Pollution Act 1974, shall be employed at all times, in order to minimise noise emissions.

5. All reasonable measures shall be employed in order to control and minimise dust emissions, including sheeting of vehicles and use of water for dust suppression.

6. There shall be no bonfires on the site.

5. Controls on construction site

The developer's attention should also be drawn to the various requirements for the control of noise on construction sites laid down in the Control of Pollution Act 1974. In order to ensure that residents are not adversely affected by air pollution and noise, the following guidance should be attached to any planning approval, failure to do so could result in formal action being taken under the Control of Pollution Act 1974:

1. All demolition and construction works and ancillary operations, including deliveries to and despatch from the site shall be confined to the following hours:

Monday to Friday	08.00 to 18.00
Saturday	09.00 to 13.00
Not at all on Sundays and Bank Holidays.	

2. The work shall be carried out in such a manner so as to comply with the general recommendations of British Standards BS 5228: Part 1: 1997, a code of practice for "Noise and Vibration Control on Construction and Open Sites" and in particular Section 10 of Part 1 of the code entitled "Control of noise and vibration".

3. All plant and machinery to be operated, sited and maintained in order to minimise disturbance. All items of machinery powered by internal combustion engines must be properly silenced and/or fitted with effective and well-maintained mufflers in accordance with manufacturers instructions.

4. The best practicable means, as defined by Section 72 of the Control of Pollution Act 1974, shall be employed at all times, in order to minimise noise emissions.

5. All reasonable measures shall be employed in order to control and minimise dust emissions, including sheeting of vehicles and use of water for dust suppression.

6. There shall be no bonfires on the site.

**Contact details:**

**Author:** Diane Cragg Development Control Officer (Mon/Tues)


**Tel No:** 01904 551657

# Archbishop Holgates School

08/01266/FULM



GIS by ESRI (UK)



Scale : 1:3750

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationery Office © Crown Copyright 2000.

Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings.

<b>Organisation</b>	Not Set
<b>Department</b>	Not Set
<b>Comments</b>	Application Site
<b>Date</b>	11 August 2008
<b>SLA Number</b>	Not Set